

PLAN SURVEYED PLOTTED CHECKED  
 NOTE BOOK NO. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 BY \_\_\_\_\_  
 FILE NAME = S:\ST-101\155008.CH33.Lasalle.County.Design\cover-schedlines.dgn

PROFILE SURVEYED PLOTTED CHECKED  
 NOTE BOOK NO. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 BY \_\_\_\_\_

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS		
STATION	FOOT	REMARKS
COUNTY HIGHWAY 33		
LT 18+89.85 TO 19+14.85	25	
LT 21+04.11 TO 22+04.11	100	
RT 17+95.89 TO 18+95.89	100	
RT 20+85.15 TO 21+10.15	25	
PROJECT TOTAL	250	
63000001		

TRAFFIC BARRIER TERMINAL, TYPE 6		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 19+14.85 TO 19+60.50	1	
LT 20+58.46 TO 21+04.11	1	
RT 18+95.89 TO 19+41.54	1	
RT 20+39.50 TO 20+85.15	1	
PROJECT TOTAL	4	
63100085		

TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 18+39.85 TO 18+89.85	1	
LT 22+04.11 TO 22+54.11	1	
RT 17+45.89 TO 17+95.89	1	
RT 21+10.15 TO 21+60.15	1	
PROJECT TOTAL	4	
63100167*		

GUARDRAIL REMOVAL		
STATION	FOOT	REMARKS
COUNTY HIGHWAY 33		
LT 17+05 TO 22+42	537	
RT 16+95 TO 21+97	502	
PROJECT TOTAL	1,039	
63200310		

FENCE REMOVAL		
STATION	FOOT	REMARKS
COUNTY HIGHWAY 33		
LT 14+50.00 TO 19+87.00	538	BARBED WIRE FENCE
RT 14+71.62 TO 19+52.00	480	BARBED WIRE FENCE
RT 20+07.00 TO 22+10.92	205	BARBED WIRE FENCE
LT 20+71.00 TO 22+58.26	188	BARBED WIRE FENCE
PROJECT TOTAL	1,411	
Z0022800*		

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 12+15.65	1	
LT 16+79.97	1	
RT 16+80.27	1	
LT 18+79.72	1	
RT 18+96.22	1	
LT & RT 21+00.00	2	
RT 22+00.00	1	
LT 22+79.88	1	
RT 22+80.34	1	
PROJECT TOTAL	10	
66600105		

PERMANENT SURVEY MARKERS, TYPE I		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
	1	WINGWALL - AS DIRECTED BY ENGINEER
PROJECT TOTAL	1	
66700205		

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
COUNTY HIGHWAY 33		
12+30.30 TO 24+50.00	224	YELLOW - CENTERLINE 2 APPLICATIONS - 4'-36" SKIP DASH
PROJECT TOTAL	224	
70300100		

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
COUNTY HIGHWAY 33		
12+30.30 TO 24+50.00	112	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	112	
70301000		

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
COUNTY HIGHWAY 33		
LT & RT 12+30.30 TO 24+50.00	2,440	NPZ - 2 LINES AT CENTERLINE (YEL)
LT & RT 12+00.00 TO 24+50.00	2,510	EDGE LINES (WHT)
PROJECT TOTAL	4,950	
78001110		

GUARDRAIL MARKERS, TYPE A		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 18+89.85 TO 19+58.67	2	
LT 20+61.63 TO 22+04.11	3	
RT 17+95.89 TO 19+38.37	3	
RT 20+41.33 TO 21+10.15	2	
PROJECT TOTAL	10	
78200410*		

GUARDRAIL MARKERS, TYPE B		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
RT 19+38.37 TO 20+41.33	4	
LT 19+58.67 TO 20+61.63	4	
PROJECT TOTAL	8	
78200420*		

TERMINAL MARKERS - DIRECT APPLIED		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 18+39.85	1	
LT 22+54.11	1	
RT 17+45.89	1	
RT 21+60.15	1	
PROJECT TOTAL	4	
78201000*		

INLET BOX, SPECIAL		
STATION	EACH	REMARKS
COUNTY HIGHWAY 33		
LT 13+00	1	WHA STANDARD 639
PROJECT TOTAL	1	
XX008455		



USER NAME = \_\_\_\_\_ DESIGNED - \_\_\_\_\_ REVISED - \_\_\_\_\_  
 DRAWN - \_\_\_\_\_ REVISED - \_\_\_\_\_  
 CHECKED - \_\_\_\_\_ REVISED - \_\_\_\_\_  
 PLOT SCALE = \_\_\_\_\_  
 PLOT DATE = \_\_\_\_\_ DATE - \_\_\_\_\_ REVISED - \_\_\_\_\_

**LASALLE COUNTY**  
**COUNTY HIGHWAY 33**  
**TOMAHAWK BRIDGE REPLACEMENT**

**SCHEDULE OF QUANTITIES**

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1365	10-00650-00-BR	LASALLE	39	4
CONTRACT NO. 87448				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT NO. BRS-1365(113)				