

PAVEMENT MARKING SCHEDULE		SHORT-TERM PAVEMENT MARKING	WORK-ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE - 4"	PAINT PAVEMENT MARKING LINE, 4"	RAISED REFLECTIVE PAVEMENT MARKERS
STATION TO STATION		FT	(SQ FT)	(FOOT)	(FOOT)	(EACH)
762+00.0	789+54.7	1102	92	6098	6098	34
789+74.3	830+75.3	1640	137	9120	9120	51
830+75.1	838+00.8	290	24	1632	1632	9
838+00.0	1345+87.8	20315	1693	116687	116687	635
1345+92.4	1356+31.4	416	35	2338	2338	13
107+70.0	65+57.5	1617	134	9134	9134	51
		25380	2115	145009	145009	793

FURNISHING AND INSTALLING PROPERTY MARKERS		QUANTITY
LOCATION	DESCRIPTION	EACH
SOUTH 1/4 CORNER SEC 6	FOUND PK NAIL	1
APPROX STA 930+70	FOUND PK NAIL	1
NORTHWEST COR. SOUTHEAST 1/4 SEC 31	FOUND PK NAIL	1
SOUTH 1/4 CORNER SEC 31	FOUND RR SPIKE	1
NORTH 1/4 CORNER SEC 6	FOUND PK NAIL	1
NORTHEAST CORNER NORTHWEST 1/4 SEC 18	FOUND RR SPIKE	1
SOUTH 1/4 CORNER SEC 19	FOUND PK NAIL	1
TOTAL		7

PAVING SCHEDULE		BITUMINOUS MATERIALS PRIME COAT	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N 70	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	AGGREGATE SHOULDERS, TYPE B
STATION TO STATION		(TON)	(TON)	(FOOT)	(FOOT)	(EACH)	(TON)	SQ YD	(TON)
762+00.0	789+54.7	796	16	334	130	36	668	7958	229
789+74.3	830+75.3	1185	24	498			995	11847	338
830+75.1	838+00.8	210	4	88			176	2097	62
838+00.0	1345+87.8	14672	293	6162			12325	146720	4198
1345+92.4	1356+31.4	296	6	125			249	2960	83
107+70.0	65+57.5	1122	23	471	375	106	943	11226	335
		18281	366	7678	505	142	15356	182808	5245

PERMANENT SURVEY MARKERS		QUANTITY
LOCATION	DESCRIPTION	EACH
780+21.9	PC	1
789+54.7 BK = 789+74.3 AH	PT	1
817+25.1	PC	1
830+75.6 BK = 830+75.1 AH	PT	1
877+00.00	PI	1
1011+00.00	PI	1
1246+00.00	PI	1
1339+29.8	PC	1
1345+87.8 BK = 1345+92.4 A	PT	1
TOTAL		9