

ROUTE NO.	SECTION	CITY	TOTAL SHEETS	SHEET NO.
	05-0001-90-AP	OREANA	46	5
FED. ROAD DIST. NO.			ILLINOIS PROJECT HPP-0913 (001)	

CONTRACT NUMBER 96537

**UTILITY ADJUSTMENTS**

Location	56400100 Fire Hydrant to be Moved Each	56500100 Dom Meter Vaults to be Moved Each	56500300 Dom Meter Vaults to be Adjusted Each	60260400 Inlet Adj w/ New Ty I, Frame CL Each	60266600 Valve Boxes to be Adjusted Each	60500040 Removing Manholes Each	60500060 Removing Inlets Each
<b>West Street</b>							
21' Rt. 501+64.0							
20' Lt. 502+09.0							
20' Lt. 503+14.0							
3' Lt. 503+43.0							
18' Lt. 503+54.0							
18' Rt. 503+94.0							
18' Lt. 503+99.0							
24' Rt. 504+04.0							
18' Lt. 504+10.0							
21' Lt. 504+67.0							
21' Rt. 505+47.0							
18' Lt. 507+35.0							
41' Lt. 507+55.0							
<b>Clay Street</b>							
15' Rt. 607+73.0							
<b>Bower Street</b>							
19' Rt. 13+20.0							
25' Lt. 13+74.0							
20' Rt. 13+92.0							
21' Rt. 14+90.0							
12' Rt. 15+47.0							
19' Rt. 15+88.0							
19' Rt. 15+90.0							
24' Lt. 16+24							
23' Lt. 16+60							
23' Lt. 16+71							
22' Rt. 16+88.0							
<b>Belle Street</b>							
19' Lt. 30+95.0							
24' Rt. 30+95.0							
24' Lt. 31+00.0							
22' Lt. 31+41.0							
24' Rt. 31+46.0							
22' Lt. 32+05.0							
25' Rt. 32+20.0							
24' Rt. 32+85.0							
21' Lt. 32+90.0							
22' Lt. 33+50.0							
23' Rt. 33+51.0							
23' Lt. 34+37.0							
22' Lt. 35+87.0							
18' Rt. 36+71.0							
21' Rt. 36+71.0							
22' Lt. 36+84.0							
22' Lt. 37+07.0							
20' Rt. 37+61.0							
22' Lt. 37+63.0							
19' Rt. 38+43.0							
22' Lt. 38+43.0							
16' Rt. 38+88.0							
17' Lt. 38+88.0							
30' Rt. 39+02.0							
25' Lt. 39+43.0							
21' Lt. 39+53.0							
17' Rt. 39+64.0							
TOTALS	1	6	29	1	5	2	8

**DRAINAGE STRUCTURES**

Location	60218400 Manhole, Type A-1C 4' Dia. Each	60223800 Manhole, Type A-1C 6' Dia. Each	60224448 Manhole, Type A-1C 7' Dia. Each	X6020088 Manhole, Type A-1C 8' Dia. Each	X6020098 Manhole, Type A-1C 9' Dia. Each	X6020108 Manhole, Type A-1C 10' Dia. Each	60242500 Inlets, Special No. 1 Each	60242600 Inlets, Special No. 2 Each	60242700 Inlets, Special No. 3 Each	60242800 Inlets, Special No. 4 Each	60242900 Inlets, Special No. 5 Each	60242802 Inlets, Special No. 6 Each	60242803 Inlets, Special No. 7 Each
<b>West Street</b>													
13.5' Lt. 501+60.0													
14.0' Rt. 501+60.0													
14.0' Lt. 502+60.0													
13.5' Rt. 502+60.0													
3.0' Lt. 503+74.0													
14.0' Lt. 506+35.5													
4.0' Lt. 506+35.5													
14.0' Rt. 506+35.5													
4.0' Lt. 507+55.0													
4.0' Lt. 507+55.0													
21.5' Lt. 507+98.0													
20.5' Rt. 507+98.0													
<b>Clay Street</b>													
13.5' Lt. 607+65.0													
CL 607+65.0													
13.5' Rt. 607+65.0													
14.0' Lt. 608+28.0													
20.0' Lt. 604+00.0													
14.0' Lt. 604+00.0													
15.0' Rt. 604+00.0													
14.0' Lt. 610+33.0													
<b>Bower Street</b>													
14.0' Rt. 12+50.0													
13.5' Lt. 12+45.0													
CL 12+45.0													
13.5' Rt. 12+45.0													
20.0' Lt. 14+74.5													
20.5' Lt. 14+93.5													
21.6' Rt. 14+93.5													
22.7' Rt. 15+36.3													
CL 15+30.0													
20.0' Lt. 15+58.0													
14.0' Lt. 15+58.0													
13.5' Lt. 17+30.0													
CL 17+30.0													
13.5' Rt. 17+30.0													
<b>Belle Street</b>													
13.5' Lt. 32+60.0													
CL 32+60.0													
13.5' Rt. 32+60.0													
13.5' Lt. 34+49.0													
CL 34+49.0													
13.5' Rt. 34+49.0													
21.1' Rt. 34+49.3													
23.8' Rt. 35+36.1													
14.0' Lt. 37+48.0													
14.0' Rt. 37+48.0													
5.0' Rt. 37+53.0													
13.5' Lt. 38+82.0													
13.5' Lt. 39+68.0													
CL 39+68.0													
13.5' Rt. 39+68.0													
<b>Outfall Bower</b>													
2+51.0													
4+14.0													
5+36.5													
7.5' Rt. 5+60.4													
7+41.5													
35.0' Rt. 7+41.5													
78.0' Rt. 7+41.5													
4+71.5													
9+26.5													
37.0' Rt. 10+08.0													
10+06.0													
11+33.0													
13+15.0													
TOTALS	8	3	3	3	2	4	7	12	4	4	1	3	2

**CURB AND GUTTER**

Location	60603300 Gutter Outlet Each	60603300 Type B-6.24 Foot	60603300 Protective Coat Sq Yd
<b>West Street</b>			
Lt. 500+49.52 - Lt. 503+36.16		243	100
Rt. 500+49.52 - Rt. 503+36.16		243	100
Lt. 503+36.16 - Lt. 14+73.65		45	15
Rt. 503+36.16 - Rt. 15+57.26		45	15
Lt. 504+20.50 - Lt. 14+75.00		44	13
Rt. 504+22.04 - Lt. 15+54.53		45	15
Lt. 504+20.50 - Lt. 507+12.34		242	100
Rt. 504+22.04 - Rt. 507+13.83		242	100
Lt. 507+12.34 - Rt. 34+74.40		44	15
Rt. 507+13.83 - Rt. 35+58.07		43	15
Lt. 507+46.37 - Lt. 34+75.52		44	15
Rt. 507+47.81 - Lt. 35+54.87		45	15
Lt. 507+46.37 - Lt. 508+02.81		1	2
Rt. 507+47.81 - Rt. 508+02.81		1	2
<b>Clay Street</b>			
Lt. 607+45.00 - Lt. 607+50.00		1	2
Rt. 607+45.00 - Rt. 607+50.00		1	2
Lt. 607+50.00 - Lt. 607+90.17		40	14
Rt. 607+50.00 - Rt. 607+42.43		42	14
Lt. 607+90.17 - Rt. 38+81.27		45	15
Rt. 607+42.43 - Rt. 34+70.00		48	16
Lt. 608+74.14 - Lt. 38+83.20		43	15
Rt. 608+76.47 - Lt. 34+70.00		47	16
Lt. 608+74.14 - Lt. 608+81.47		1	2
Rt. 608+76.47 - Rt. 608+81.47		1	2
<b>Bower Street</b>			
Lt. 12+80.00 - Lt. 12+85.00		1	2
Rt. 12+80.00 - Rt. 12+85.00		1	2
Lt. 12+85.00 - Rt. 14+73.65		184	64
Rt. 12+85.00 - Lt. 14+75.11		190	64
Lt. 15+57.26 - Rt. 17+35.00		178	61
Rt. 15+54.53 - Lt. 17+35.00		175	60
Lt. 17+35.00 - Lt. 17+40.00		1	2
Rt. 17+35.00 - Lt. 17+40.00		1	2
<b>Belle Street</b>			
Lt. 30+32.94 - Lt. 30+35.44		1	2
Rt. 30+36.47 - Rt. 30+41.47		1	2
Lt. 30+41.47 - Rt. 34+74.40		433	148
Rt. 30+35.44 - Lt. 34+75.52		440	151
Lt. 35+58.07 - Rt. 38+81.27		323	110
Rt. 35+54.87 - Lt. 38+83.20		323	110
Lt. 34+70.00 - Lt. 34+75.00		1	2
Rt. 34+70.00 - Rt. 34+75.00		1	2
TOTALS	14	4044	1407

**SLOTTED DRAIN  
12" with 2 1/2" SLOT**

Location	Foot
13.75' Lt. 506+11.0 - 13.75' Lt. 506+60.0	40
13.75' Rt. 506+11.0 - 13.75' Rt. 506+60.0	40
13.75' Lt. 37+23.5 - 13.75' Lt. 37+72.5	40
13.75' Rt. 37+23.5 - 13.75' Rt. 37+72.5	40
TOTAL	160

**WATER SERVICE LINE, 1"**

Location	Foot
<b>Clay Street</b>	
15' Rt. 607+73.0	10
<b>Bower Street</b>	
19' Rt. 13+20.0	10
25' Lt. 13+74.0	8
21' Rt. 14+90.0	15
<b>Belle Street</b>	
22' Lt. 36+84.0	11
22' Lt. 37+07.0	8
TOTAL	62

**WATER VALVES, 6"**

Location	Each
<b>Belle Street</b>	
32' Lt. 34+43.0	1

**FENCING TO BE REMOVED AND RE-ERECTED**