

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	2023
20800150	TRENCH BACKFILL	CU YD	23
25000100	SEEDING, CLASS 1	ACRE	0.56
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	56
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	56
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	56
25100115	MULCH, METHOD 2	ACRE	0.56
25200100	SODDING	SG YD	290
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	61
28000305	TEMPORARY DITCH CHECKS	FOOT	48
28000400	PERIMETER EROSION BARRIER	FOOT	1246
28000500	INLET AND PIPE PROTECTION	EACH	12
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	2269
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	177
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1051
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SG YD	185
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	904
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	254
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	21
42001300	PROTECTIVE COAT	SG YD	1012
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SG FT	2082
42400800	DETECTABLE WARNINGS	SG FT	240
44000100	PAVEMENT REMOVAL	SG YD	2064
50105220	PIPE CULVERT REMOVAL	FOOT	181
54200220	PIPE CULVERTS, CLASS C, TYPE 1 15"	FOOT	24
54200223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	7
54215550	METAL END SECTIONS 15"	EACH	2
54215553	METAL END SECTIONS 18"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	174
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	156
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	240
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60240385	INLETS, TYPE B, WITH SPECIAL FRAME AND GRATE	EACH	1
60500060	REMOVING INLETS	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1274.5
60607200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.18 (SPECIAL)	FOOT	166.5
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	273.5
60611700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL)	FOOT	313.5
60619310	CONCRETE MEDIAN SURFACE, 4 INCH (SPECIAL)	SQ FT	207
67100100	MOBILIZATION	L SUM	1
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	255
72000100	SIGN PANEL - TYPE 1	SQ FT	135
72000200	SIGN PANEL - TYPE 2	SQ FT	44
72900100	METAL POST - TYPE A	FOOT	186
72900200	METAL POST - TYPE B	FOOT	124
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	45
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	891
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	54
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	138
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	210
78200300	PRISMATIC CURB REFLECTOR	EACH	51
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	320
LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SG YD	372
X0325680	HOT-MIX ASPHALT SIDEWALK	SG FT	3897
X4404700	SIDEWALK REMOVAL (SPECIAL)	SG FT	4660
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	1
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	6
X7800200	PAINT PAVEMENT MARKING CURB	FOOT	305
Z0013798	CONSTRUCTION LAYOUT	L SUM	1
Z0042500	POST, SPECIAL	EACH	12
Z0058608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	18

LAST SAVED: 12/28/2010 12:54:15 PM
FILE NAME: C:\Users\jshirron\Documents\2010\08\08-00060-00-PV.dwg
C:\Users\jshirron\Documents\2010\08\08-00060-00-PV.dwg

FILE NAME: C:\Users\jshirron\Documents\2010\08\08-00060-00-PV.dwg	USER NAME: jshirron	DESIGNED: -	REVISED: 12/20/10
		DRAWN: -	REVISED: -
		CHECKED: -	REVISED: -
		DATE: -	REVISED: -

HORNER & SHIRRON, INC.
ENGINEERS
www.HornerShirron.com

Q Fallon
F I L L I N G

SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET NO. 1 OF 1	SHEETS	STA. TO STA.

F.A.U. 9170	TOTAL SHEETS	SHEET NO.
PORTER / SIMMONS ROADS	36	3
SECTION 08-00060-00-PV		
CONTRACT 97408		