



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 20, 2021

SUBJECT FAI Route 57 (I-57)
Project NHPP-LW6L(067)
Section 2021-101-BR
Cook County
Contract No. 62P29
Item No. 11, January 21, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions
2. Added page 145 to the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

PERFORMANCE GRADED ASPHALT BINDER (BDE)..... 127
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)..... 132
STEEL COST ADJUSTMENT (BDE)..... 133
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 136
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 136
TRAINING SPECIAL PROVISIONS (BDE) 137
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION..... 140
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 142
WEEKLY DBE TRUCKING REPORTS (BDE)..... 142
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 142
WORKING DAYS (BDE) 144
CLEAN AND RESEAL RELIEF JOINT 145

Revised 12/20/2021

CLEAN AND RESEAL RELIEF JOINT

Description. This item shall consist of furnishing all equipment and labor for removal and disposal of any existing joint material, cleaning interior vertical surfaces of the joint, repairing any existing dowel bars as specified by the Engineer, and installation of new joint as specified in the plans or herein.

In case of HMA overlay on each side of the relief joint, the contractor shall mark the location of the joint for future reference before overlaying. The existing Preformed Joint Fillet (PJF) shall be left in place. If applicable, the existing 4" Premolded Expansion Seal (PJS) shall be removed. The joint shall be resealed with Hot-Poured Joint Sealer per Standard Specifications Articles 420.12 and 1050.02. The HMA overlay shall be placed as shown on the plans overlaying the joint location. After the curing period, the HMA shall be saw cut over the existing relief joint and sealed.

Measurement. Clean and Reseal Relief Joint will be measured for payment in place and the length computed in feet.

Basis of Payment. The work specified herein, as shown on the plans and as directed by the Engineer, shall be paid for at the contract unit price per feet for CLEAN AND RESEAL RELIEF JOINT

Added 12/20/2021