SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	AS-BUILT QUANTITY
AR125962	RELOCATE BASE MOUNTED LIGHT	EA.	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150520	MOBILIZATION	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	900	
AR152540	SOIL STABILIZATION FABRIC	S.Y.	1,733	
AR156520	INLET PROTECTION	EA.	5	
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	830	
AR401613	BIT, SURF. CSE.-METHOD I, SUPERPAVE	TON	390	
AR401900	REMOVE BITUMINOUS PAVEMENT	S.Y.	702	
AR501600	PCC SIDEWALK	S.F.	1,041	
AR602510	BITUMINOUS PRIME COAT	GAL.	490	
AR603510	BITUMINOUS TACK COAT	GAL.	163	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	830	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	830	
AR701006	6" PVC STORM SEWER	L.F.	36	
AR701512	12" RCP, CLASS IV	L.F.	191	
AR701900	REMOVE PIPE	L.F.	74	
AR701960	RELOCATE PIPE	L.F.	38	
AR751411	INLET-TYPE A	EA.	3	
AR751540	MANHOLE 4'	EA.	2	
AR751900	REMOVE INLET	EA.	2	
AR800457	UTILITY INVESTIGATION	L.S.	1	
AR901510	SEEDING	ACRE	0.6	
AR908510	MULCHING	ACRE	0.6	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	SAFETY PLAN AND GENERAL NOTES
4	EXISTING SITE AND DEMOLITION PLAN
5	CONSTRUCTION PLAN
6	GRADING PLAN
7	TYPICAL SECTION AND DETAILS
8	MARKING AND LIGHT RELOCATION PLAN
9	ELECTRICAL DETAILS
10	ELECTRICAL NOTES
11	EXISTING HIGH VOLTAGE WIRING SCHEMATIC

HANSON
Engineering | Planning | Allied Services

Offices Nationwide
www.hanson-inc.com

Hanson Professional Services Inc.
1525 S. 6th Street
Springfield, IL 62703
phone: 217-788-2450
fax: 217-788-2503

Illinois Licensed
Professional Service Corporation
#184-001084

SHELBY COUNTY AIRPORT

P. O. BOX 295
ASSUMPTION, IL. 62510

CONSTRUCT ACCESS TO SNOW REMOVAL EQUIPMENT STORAGE BUILDING

IDA No: 2H0-4341
SBG No: 3-17-SBGP-XX

CONTRACT No: SE005

NO.	DATE	DESCRIPTION		
		DES	DWN	REV

ISSUE: DECEMBER 4, 2014
PROJECT NO: 13A0082
CAD FILE: G-002SOQ.DWG
DESIGN BY: KBS 11/14/2014
DRAWN BY: KBS 11/14/2014
REVIEWED BY: RAW 12/04/2014

SHEET TITLE

SUMMARY OF QUANTITIES AND INDEX TO SHEETS

DEC 05, 2014 1:27 PM SCHWE01296
I:\13JOBS\13A0082\13A0082D\CAD\AIRPORT\SHEETG-002SOQ.DWG