

COOK COUNTY WESTBOUND SIGN SCHEDULE

SIGN NO.	STATION	LEGEND/DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL-TYPE 1 (SQ FT)	REMOVE SIGN PANEL-TYPE 2 (SQ FT)	REMOVE SIGN PANEL-TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A EACH	REMOVE SIGN PANEL ASSEMBLY - TYPE B EACH	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	SIGN PANEL TYPE 3 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REMOVAL OF SIGN LIGHTING, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
WB-TR-36*	354+50	EXIT 12 - US 20 WEST - LAKE ST YORK RD - 1 MILE	23.5	12.5	23.5	12.5			293.8					293.8			1.0
WB-TR-37*	354+50	EXIT 13B - IL 64 WEST - NORTH AVE	17.0	12.5	17.0	12.5			212.5					212.5			1.0
WB-WP-37A	359+74	W4-1R	4.0	4.0	4.0	4.0							16.0		18.0		
WB-WP-38	368+50	EXIT - 13A	7.5	5.0	7.0	5.0								35.0	36.0		
WB-TR-39*	373+00	EXIT 12 - US 20 WEST - LAKE ST - 1 1/2 MILES	11.5	12.5	11.5	12.5			143.8					143.8			1.0
WB-TR-40*	373+00	EXIT 13B - IL 64 WEST - NORTH AVE - 1/4 MILE	13.5	12.5	13.5	12.5			168.8					168.8			1.0
WB-TR-41*	373+00	EXIT 13A - US 20 EAST - LAKE ST	14.0	12.5	14.0	12.5			175.0					175.0			1.0
WB-PM-41A	373+00	W13-3 (30 MPH)	3.0	4.0	4.0	5.0		12.0				20.0					
WB-CL-42*	383+90	IL 64 WEST - THRU TRUCKS - USE EXIT 12	15.5	10.0	15.5	10.0			155.0					155.0			1.0
WB-TR-43	391+50	EXIT 13B - IL 64 WEST - NORTH AVE - 3/4 MILE	14.5	12.5	14.5	12.5			181.3					181.3			1.0
WB-TR-44	391+50	EXIT 13A - US 20 EAST - LAKE ST - 1/4 MILE	12.5	11.5	11.5	12.5			143.8					143.8			1.0
WB-PM-44A	391+50	R2-1 (55 MPH)	4.0	5.0	4.0	5.0		20.0				20.0					
WB-GM-45	395+40	TO I 294 NORTH TOLLWAY - MILWAUKEE - EXIT 13A	13.5	9.0	13.5	9.0			121.5					121.5			
WB-TS-45A1	396+91	M3-4	2.5	1.3	2.5	1.3				1.0						18.0	
WB-TS-45A2	396+91	M1-1-3 (I 290)	PER MUTCD	STD (9FT ²)	PER MUTCD	STD (9FT ²)				1.0		3.1					
WB-GM-46*	402+30	TO IL 64 EAST - NORTH AVE - EXIT 13A	13.5	10.0	13.5	10.0			135.0				9.0	135.0			
WB-WP-46A	408+00	W4-1R	4.0	4.0	4.0	4.0						1.0	16.0		18.0		
WB-WP-47	411+50	EXIT - 14A	7.5	5.0	7.0	5.0						1.0	35.0		36.0		
WB-TS-47A	412+35	W13-3 (30 MPH)	3.0	4.0	4.0	5.0						1.0	20.0			18.0	
WB-BM-48	415+40	EXIT 14A - WEST - ST CHARLES RD	20.5	8.0	20.5	8.0			164.0					164.0			1.0
WB-BM-48A	415+40	TRUCKS USE - 2 RIGHT LANES	15.0	5.5	15.0	5.5			82.5					82.5			
WB-WP-48B	417+88	W4-1R	4.0	4.0	4.0	4.0						1.0	16.0		18.0		
WB-WP-49	422+00	EXIT - 14B	7.5	5.0	7.0	5.0						1.0	35.0		36.0		
WB-TS-49A	424+05	W13-3 (30 MPH)	3.0	4.0	4.0	5.0						1.0	20.0			18.0	
WB-TR-50*	426+20	EXIT 13A - US 20 EAST - LAKE ST - 1 MILE	11.5	12.5	11.5	12.5			143.8					143.8			1.0
WB-TR-51*	426+20	EXIT 14A - WEST - ST CHARLES RD - 1/4 MILE	17.5	12.5	17.5	12.5			218.8					218.8			1.0
WB-TR-52*	426+20	EXIT 14B - EAST - ST CHARLES RD	17.5	12.5	17.5	12.5			218.8					218.8			1.0
WB-PM-52A	426+20	TRUCKS - USE - 2 - RIGHT - LANES	4.0	5.0	4.0	5.0		20.0				20.0					
WB-GM-52B	433+00	WESTBOUND - ST CHARLES RD - TRUCKS PROHIBITED	16.0	6.0	17.0	7.0			96.0					119.0			
WB-GM-53	435+50	EXIT 14B - EAST - ST CHARLES RD - 1/4 MILE	19.0	12.0	19.0	12.0			228.0					228.0			
WB-TS-53A	437+73	R2-1 (55 MPH)	4.0	5.0	4.0	5.0						1.0	20.0			18.0	
WB-TS-53B1	441+93	M3-4	2.5	1.3	2.5	1.3				1.0			3.1			18.0	
WB-TS-53B2	441+93	M1-1-3 (I 290)	PER MUTCD	STD (9FT ²)	PER MUTCD	STD (9FT ²)				1.0		9.0					
WB-WP-53C	464+91	W4-3R	4.0	4.0	4.0	4.0						1.0	16.0		18.0		
WB-WP-54	470+50	EXIT - 15B	7.5	5.0	7.0	5.0						1.0	35.0		36.0		
WB-PM-54A1	471+03	M3-4	2.5	1.3	2.5	1.3		3.1					3.1				
WB-PM-54A2	471+03	M1-1-3 (I 290)	PER MUTCD	STD (9FT ²)	PER MUTCD	STD (9FT ²)		9.0					9.0				
WB-TS-54B	472+56	W13-3 (40 MPH)	3.0	4.0	4.0	5.0						1.0	20.0			18.0	
WB-TR-55	474+80	EXITS 14A-B - ST CHARLES RD - 1 MILE	19.0	12.0	19.0	12.0			228.0					228.0			1.0
WB-TR-56	474+80	"EXIT 15B - I 294 NORTH TOLLWAY - MILWAUKEE	20.5	10.0	20.5	10.0			205.0					205.0			1.0
WB-TR-57	484+20	I 290 WEST - ROCKFORD	22.5	10.5	22.5	10.5			236.3					236.3			1.0
WB-TR-58	484+20	"EXIT 15B - I 294 NORTH TOLLWAY - MILWAUKEE	20.0	10.5	20.0	10.5			210.0					210.0			1.0
WB-TS-58A1	486+00	R3-4	4.0	4.0	4.0	4.0							1.0	16.0			
WB-TS-58A2	486+00	EXCEPT - AUTHORIZED - VEHICLES	4.0	2.7	4.0	2.7							1.0	10.6			
COOK COUNTY WESTBOUND SUBTOTAL							13	52	3762	4	14	37	232	3924	216	108	16

*EXISTING SIGN DIMENSIONS NOT AVAILABLE; PROPOSED SIGN DIMENSIONS USED

FILE NAME =	DESIGNED - SEW	REVISED -	 <p>LIN ENGINEERING, LTD. Consulting Engineers Chicago, Illinois Westmont, Illinois</p>	<p align="center">STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</p>	<p align="center">SCHEDULE OF QUANTITIES</p>				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILES#	DRAWN - SEW	REVISED -							290	2009-099BR	COOK/DUPAGE	394	312
USER NAME = #USER#	CHECKED - FML	REVISED -			SCALE: N.T.S. SHEET NO. 3 OF 4 SHEETS STA. TO STA.					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			
PLOT DATE = #DATE#	DATE - 12/2009	REVISED -								CONTRACT NO. 60157			