SIGN DETAIL
1:75

EB-CL-41
STA. 433+40

SIGN NUMBER	name
WIDTH x HGHT.	14'-6" x 9'-6"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT
M1_1	0	25.7	64	36	36

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)							LENGTH	SERIES/SIZE
T	O							ClearviewHwy-5-W-R
6	15.2						18.5	10
W	E	S	T					ClearviewHwy-5-W
93.3	117	127.8	139.2				54.5	15,12
T	O	L	L	W	A	Y		ClearviewHwy-5-W-R
85.1	94.3	106.5	115	122.4	136.9	147.3	70.9	10
A	u	r	o	r	a			ClearviewHwy-5-W-R
45.3	63.8	79.7	90.1	106.9	116.9		83.5	16/13
E	X	I	T	1	5	A		ClearviewHwy-5-W
45.3	55.5	69.2	75.1	93.8	105.7	119.8	88.6	12,15

FILE NAME =	DESIGNED - SEW	REVISED -
$FILEL$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 12/2009	REVISED -

LIN ENGINEERING, LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 16 OF 58 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	2009-099BR	COOK/DUPAGE	394	344
		CONTRACT NO. 60I57		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		