

CONTRACT 60K10
TEMPORARY INFORMATION SIGNING - STAGE 2

STATION	LEGEND/DESCRIPTION	PANEL		PANEL
		COVER DIMENSIONS		COVER AREA
		WIDTH (FT)	HEIGHT (FT)	(SQ FT)
795+00	HARLEM AVE EXIT ONLY	3.0	19.5	58.5
809+40	EXIT ONLY	2.5	18.0	45.0
836+30	EXIT ONLY	2.5	18.0	45.0
TOTAL				148.5

CONTRACT 60K10
TEMPORARY PAVEMENT MARKING AND TEMPORARY IMPACT ATTENUATOR SCHEDULE

STAGE	WET REFLECTIVE TEMPORARY TAPE - LETTERS AND SYMBOLS	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	TEMPORARY PAVEMENT MARKING - LINE 6"	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 12 INCH	PAVEMENT MARKING REMOVAL	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 4 INCH	EPOXY PAVEMENT MARKING - LINE 8 INCH	EPOXY PAVEMENT MARKING - LINE 5 INCH	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
	(SQ FT)	(FOOT)	(FOOT)		(FOOT)	(FOOT)	(SQ FT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)
1		30,383	1,969	10,298	12,491	1,494	3,310					3	
2	109	36,252	7,296	16,393	7,717	338	12,706					5	3
RESURFACING		26,697	14,369		6,992	1,794		1,000	160,241	9,867	61,200		
TOTAL	109	93,332	23,634	26,691	27,201	3,626	16,016	1,000	160,241	9,867	61,200	8	3

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...\\ppln\ABC_C2_sch_03.dgn	DRAWN - TMB	REVISED -			290	(3131, ETC., 3435)RS-6	COOK	215	19				
USER NAME = tblank	CHECKED - JMM	REVISED -			SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.				CONTRACT NO. 60K10				
PLOT DATE = 1/25/2010	DATE - 1/25/10	REVISED -			FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT				