SIGN DETAIL

1:75

EB-BM-88
STA. 822+10

SIGN NUMBER	
WIDTH x HGHT.	18'-0" x 8'-0"
BORDER WIDTH	2"
CORNER RADIUS	12"
MOUNTING	Overhead
BACKGROUND	TYPE: Reflective
	COLOR: Green
LEGEND/BORDER	TYPE: Reflective
	COLOR: White/White

SYMBOL	ROT	X	Y	WID	HT

Panel Style: sign_default.ssi
Dimensions are in inches.tenths

Letter locations are panel edge to lower left corner

LETTER POSITIONS (X)												LENGTH	SERIES/SIZE
L	E	F	T										ClearviewHwy-5-W
18	28.8	40.5	50.6									41.2	12
E	X	I	T	2	3	A							ClearviewHwy-5-W
70.1	80.4	94.1	100	118.6	133	147.1						91	12,15
A	u	s	t	i	n		B	l	v	d			ClearviewHwy-5-W-R
36.1	54.6	69.1	81.8	93.4	101.8	112.9	130.1	146.7	153.7	168.4		143.9	16/13
L	E	F	T										ClearviewHwy-5-W
48.5	59.3	71	81.1									41.2	12
12	M	I	L	E									ClearviewHwy-5-W
101.7	133.1	146.2	152.1	161.2								65.8	15,10

FILE NAME =	DESIGNED - SEW	REVISED -
$FILE$	DRAWN - SEW	REVISED -
USER NAME = $USER$	CHECKED - FML	REVISED -
PLOT DATE = $DATE$	DATE - 1/25/10	REVISED -

LIN ENGINEERING,LTD.
Consulting Engineers
Chatham, Illinois Westmont, Illinois

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNING DETAILS

SCALE: N.T.S. | SHEET NO. 14 OF 34 SHEETS | STA. | TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
290	(3131, ETC., 3435) RS-6	COOK	215	146
		CONTRACT NO. 60K10		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		