

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNS	SURVEILLANCE
					90% FED 10% STATE	90% FED 10% STATE	90% FED 10% STATE
					URBAN	CONSTRUCTION TYPE CODE	
					1000-2A	Y002-1C	Y032-1F
**	44004260	PAVED SHOULDER REMOVAL (SPECIAL)	SQ YD	1,607	1,607		
	44200569	CLASS A PATCHES, TYPE III, 11 INCH	SQ YD	22	22		
	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	274	274		
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	8,961	8,961		
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	2,219	2,219		
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	4,593	4,593		
	44213000	PATCHING REINFORCEMENT	SQ YD	22	22		
	44213200	<i>SAW CUTS</i>	FOOT	40	40		
	48300100	PORTLAND CEMENT CONCRETE SHOULDERS 6"	SQ YD	40	40		
Δ	55039700	STORM SEWERS TO BE CLEANED	FOOT	8,112	8,112		
	60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	180	180		
	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	180	180		
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	326	326		
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	443	443		
*	63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	25	25		
	63200305	STEEL PLATE BEAM GUARDRAIL REMOVAL	FOOT	25	25		
	64200105	SHOULDER RUMBLE STRIP	FOOT	46,896	46,896		
	67100100	MOBILIZATION	L SUM	1	1		
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	17	17		
*	72000105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	58		58	
*	72000205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	1,154		1,154	
*	72000305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	8,153		8,153	
*	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5		5	
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	252		252	
*	73000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	576		576	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	164	164		

Δ NON-PARTICIPATING
• SPECIALTY ITEMS
** FOR LOCATIONS AND EXTENT OF WORK NOT SHOWN IN THE PLANS, THE CONTRACTOR SHALL COORDINATE WITH THE ENGINEER AND CONTACT RICK WANNER, ROADSIDE DEVELOPMENT ARCHITECT, IDOT ROADSIDE DEVELOPMENT UNIT AT (847) 705-4172 AT LEAST 72 HOURS PRIOR TO STARTING WORK.

FILE NAME =	DESIGNED - AJP	REVISED -	benesch	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#	DRAWN - TMB	REVISED -						290	(2525, ETC., 2727)RS-8	COOK	201	4	
USER NAME = #USER#	CHECKED - JMM	REVISED -			SCALE: N.T.S.	SHEET NO. 2 OF 5 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60K11		
PLOT DATE = #DATE#	DATE - 1/25/10	REVISED -											