

DRAINAGE STRUCTURE STA - O/S*	DRAINAGE STRUCTURES TO BE CLEANED
FROM EB ALIGNMENT	EACH
874+80 - 40' R	1
880+12 - 75' R	1
884+00 - 45' R	1
898+50 - 45' R	1
904+50 - 150' R	1
908+25 - 100' R	1
911+85 - 0'	1
917+25 - 20' R	1
923+50 - 0'	1
930+00 - 0'	1
936+35 - 0'	1
943+85 - 0'	1
950+75 - 5' L	1
959+30 - 15' R	1
965+20 - 5' L	1
973+50 - 5' L	1
979+60 - 5' L	1
986+06 - 5' L	1
991+80 - 5' L	1
997+32 - 5' L	1
1003+89 - 5' L	1
1012+57 - 5' L	1
1019+15 - 5' L	1
1025+60 - 5' L	1
1031+40 - 5' L	1
1037+10 - 5' L	1
1044+59 - 6' R	1
1050+56 - 5' L	1
1059+91 - 5' L	1
1069+18 - 124' L	1
JOB SITE	312
TOTAL	342

UPSTREAM MH STA - O/S*	DOWNSTREAM MH STA - O/S*	PIPE SIZE	LOCATION DIST. FROM US MH	APPROXIMATE VOLUME OF PATCHING REQUIRED	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 IN.)	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 IN.)
FROM EB ALIGNMENT	FROM EB ALIGNMENT	H X W	FT	CU. YD	SQ. FT.	SQ. FT.
874+80 - 40' R	868+00 - 40' R	4'6" x 4'2"	398.2	0.3	2.0	-
884+00 - 45' R	880+12 - 75' R	4'2" x 3'11"	176.0	0.3	-	16.0
884+00 - 45' R	880+12 - 75' R	4'6" x 4'2"	369.7	1.5	-	40.0
884+00 - 45' R	880+12 - 75' R	4'6" x 4'2"	403.9	1.5	-	40.0
930+00 - 0'	936+35 - 0'	4'4" x 4'	232.4	1.5	36.0	-
936+35 - 0'	943+85 - 0'	4'6" x 4'2"	428.5	1.0	24.0	-
991+80 - 5' L	997+32 - 5' L	6'6" x 6'	114.5	0.3	2.0	-
1031+40 - 5' L	1037+10 - 5' L	7'5" x 6'10"	68.3	0.3	2.0	-
1031+40 - 5' L	1037+10 - 5' L	8'6" x 6'7"	523.9	0.3	2.0	-
1037+10 - 5' L	1044+59 - 6' R	8'6" x 6'7"	142.3	0.3	2.0	-
1037+10 - 5' L	1044+59 - 6' R	8'6" x 6'7"	148.0	1.0	-	32.0
1050+56 - 5' L	1059+91 - 5' L	8'7" x 7'4"	462.5	1.0	-	32.0
TOTAL					70	160

* THE STATIONS PROVIDED FOR THE PROPOSED CLEANING AND REPAIR LOCATIONS ARE BASED ON PREVIOUS PLANIMETRICS AND AERIAL PHOTOGRAPHY, AND IS NOT THE RESULT OF A GROUND SURVEY. THE STATIONING IS PROVIDED FOR REFERENCE PURPOSES ONLY.

FILE NAME =	DESIGNED - SGL	REVISED -	 LIN ENGINEERING LTD. Consulting Engineers <small>Crain, Illinois Westmont, Illinois</small>	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FILEL	DRAWN - SGL	REVISED -			290	(2727, ETC., 3131) RS-7	COOK	216	20				
USER NAME = #USER*	CHECKED - FML	REVISED -			CONTRACT NO. 60G53								
PLOT DATE = #DATE*	DATE - 1/25/10	REVISED -			SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				