

CODE NO.	ITEM	UNIT	URBAN	
			TOTAL QUANTITY	CONSTRUCTION CODE
			100% STATE	0005
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	20	20
20800150	TRENCH BACKFILL	CU YD	22.7	22.7
•21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SO YD	507	507
•21400100	GRADING AND SHAPING DITCHES	FOOT	306	306
25000100	SEEDING, CLASS 1	ACRE	0.2	0.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.4	0.4
25100125	MULCH, METHOD 3	ACRE	0.1	0.1
•25100900	TURF REINFORCEMENT MAT	SO YD	183	183
28000400	PERIMETER EROSION BARRIER	FOOT	280	280
28000500	INLET AND PIPE PROTECTION	EACH	4	4
28100105	STONE RIPRAP, CLASS A3	SO YD	14.3	14.3
28200200	FILTER FABRIC	SO YD	14.3	14.3

CODE NO.	ITEM	UNIT	URBAN	
			TOTAL QUANTITY	CONSTRUCTION CODE
			100% STATE	0005
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SO YD	93.3	93.3
35101400	AGGREGATE BASE COURSE, TYPE B	TON	42.3	42.3
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	282	282
40600300	AGGREGATE (PRIME COAT)	TON	1.5	1.5
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	213.3	213.3
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	156.2	156.2
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	63.4	63.4
42000100	PORTLAND CEMENT CONCRETE PAVEMENT 6"	SO YD	93.3	93.3
42001300	PROTECTIVE COAT	SO YD	253	253
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1162	1162
44000100	PAVEMENT REMOVAL	SO YD	326	326
44000300	CURB REMOVAL	FOOT	56	56
44000400	CUTTER REMOVAL	FOOT	170	170
X4404700	SIDEWALK REMOVAL (SPECIAL)	SO FT	571	571
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SO YD	21.3	21.3

FILE NAME - D64E315-sh1802-500.dgn	USER NAME - Stevak	DESIGNED - R.H.D.	REVISED -
		DRAWN - S.D.K.	REVISED -
	PLOT SCALE = 1:8000' / in.	CHECKED - R.H.D.	REVISED -
Default	PLOT DATE = 12/19/2013	DATE - 12/19/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
LINCOLN'S TOMB SITE RENOVATIONS**

SCALE:	SHEET 2 OF 16 SHEETS	STA.	TO STA.	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
					PARK ROADS	SANGAMON	16	2
							CONTRACT NO. 46315	
ILLINOIS FED. AID PROJECT								

JOB NO. 250-081-K3 VASCONCELLES ENGINEERING CORP. DESIGN FIRM REGISTRATION NUMBER 184-002107