


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION		
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021		
* 25100135	MULCH, METHOD 4	ACRE	0.75	0.75								
* 25100630	EROSION CONTROL BLANKET	SO YD	3475	3475								
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	1530	1530								
* 25200110	SODDING, SALT TOLERANT	SO YD	331	331								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	75	75								
28000400	PERIMETER EROSION BARRIER	FOOT	2006	2006								
28000510	INLET FILTERS	EACH	40	40								
28100107	STONE RIPRAP, CLASS A4	SO YD	2085		1978		107					
28200200	FILTER FABRIC	SO YD	2085		1978		107					
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SO YD	1872	1872								
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SO YD	10042	10042								
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	877	877								
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	132	132								
40600300	AGGREGATE (PRIME COAT)	TON	3	3								

\* SPECIALTY ITEMS

 <b>Bollinger, Lach &amp; Associates, Inc.</b> ITASCA, ILLINOIS	USER NAME * #USER#	DESIGNED - MTC	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER</b> <b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * #SCALE#	DRAWN - MTC	REVISED -		307	541Y-3-B	COOK	143	5			
	PLOT DATE * #DATE#	CHECKED - JIP	REVISED -		SCALE: NONE    SHEET NO. 2 OF 18 SHEETS    STA.    TO STA.					CONTRACT NO. 60J11		
		DATE - 12/20/2013	REVISED -		ILLINOIS FED. AID PROJECT							