


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION	
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	147	147							
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SO YD	8896	8896							
42001300	PROTECTIVE COAT	SO YD	10830	10830							
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SO YD	404	404							
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	94	94							
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	5412	5412							
42400800	DETECTABLE WARNINGS	SO FT	161	141	20						
44000100	PAVEMENT REMOVAL	SO YD	12986	12986							
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	95	95							
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3083	3083							
44000600	SIDEWALK REMOVAL	SO FT	5349	5349							
44003100	MEDIAN REMOVAL	SO FT	177	177							
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SO YD	181	181							
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1						

* SPECIALTY ITEMS

 Bollinger, Lach & Associates, Inc. <small>PARCA, ILLINOIS</small>	USER NAME : *USER*	DESIGNED - MTC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER SUMMARY OF QUANTITIES	F.A.P. RTE. 307	SECTION 541Y-3-B	COUNTY COOK	TOTAL SHEETS 143	SHEET NO. 6			
	PLOT SCALE : *SCALE*	DRAWN - MTC	REVISED -			CONTRACT NO. 60J11							
	PLOT DATE : *DATE*	CHECKED - JJP	REVISED -			SCALE: NONE	SHEET NO. 3 OF 18 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT				
	DATE - 12/20/2013	REVISOR -	REVISED -										