


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021
50200100	STRUCTURE EXCAVATION	CU YD	180		180					
50200300	COFFERDAM EXCAVATION	CU YD	4555		4361		194			
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1		1					
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1		1					
50201123	COFFERDAM (TYPE 2) (LOCATION - 3)	EACH	1		1					
50300225	CONCRETE STRUCTURES	CU YD	1430.2		1410.6		19.6			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1056.3		1056.3					
50300260	BRIDGE DECK GROOVING	SQ YD	2463		2463					
50300265	SEAL COAT CONCRETE	CU YD	1568.2		1520.3		47.9			
50300280	CONCRETE ENCASEMENT	CU YD	9.8		9.8					
50300300	PROTECTIVE COAT	SQ YD	3357		3357					
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1					
50500505	STUD SHEAR CONNECTORS	EACH	15630		15630					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	365080		363440		1640			

* SPECIALTY ITEMS

 Bollinger, Lach & Associates, Inc. <small>TRASCA, ILLINOIS</small>	USER NAME * #USER*	DESIGNED - MTC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * #SCALE*	DRAWN - MTC	REVISED -					307	541Y-3-B	COOK	143	7
	PLOT DATE * #DATE*	CHECKED - JIP	REVISED -					CONTRACT NO. 60J11				
	DATE - 12/20/2013	REVISOR -	REVISED -					SCALE: NONE	SHEET NO. 4 OF 18 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT