

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2514			2514				
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4014			4014				
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	98			98				
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 IC	FOOT	2546			2546				
* 87702201	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 18 FT. AND 34 FT.	EACH	1			1				
* 87702245	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 20 FT. AND 55 FT.	EACH	1			1				
* 87702520	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 34 FT. AND 30 FT.	EACH	1			1				
* 87704516	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 30 FT.	EACH	1			1				
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8			8				
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4			4				
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	54			54				
* 87900200	DRILL EXISTING HANDHOLE	EACH	2			2				
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	11			11				
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	10			10				

* SPECIALTY ITEMS

FILE NAME * #FILE#



Bollinger, Lach & Associates, Inc.
TASCA, ILLINOIS

USER NAME * #USER#	DESIGNED - MTC	REVISED -
PLOT SCALE * #SCALE#	DRAWN - MTC	REVISED -
PLOT DATE * #DATE#	CHECKED - JJP	REVISED -
	DATE - 12/20/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER
SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 13 OF 18 SHEETS STA. TO STA.

F.A.P. RTE. 307	SECTION 541Y-3-B	COUNTY COOK	TOTAL SHEETS 143	SHEET NO. 11E
CONTRACT NO. 60J11				
ILLINOIS FED. AID PROJECT				