


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2				
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2				
* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	21			21				
* 88600700	PREFORMED DETECTOR LOOP	FOOT	798			798				
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	6			6				
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1			1				
* 89501400	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT	EACH	2							2
* 89501510	RELOCATE EXISTING FLASHING BEACON	EACH	2							2
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	5102			5102				
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1			1				
* 89502378	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	3			3				
* 89502380	REMOVE EXISTING HANDHOLE	EACH	10			8	2			
* 89502382	REMOVE EXISTING DOUBLE HANDHOLE	EACH	2			2				
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	8			8				

\* SPECIALTY ITEMS

 <b>Bollinger, Lach &amp; Associates, Inc.</b> ITASCA, ILLINOIS	USER NAME * #USER#	DESIGNED - MTC	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER</b> <b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * #SCALE#	DRAWN - MTC	REVISED -		307	541Y-3-B	COOK	143	11F			
	PLOT DATE * #DATE#	CHECKED - JJP	REVISED -		SCALE: NONE    SHEET NO. 14 OF 18 SHEETS    STA.    TO STA.					CONTRACT NO. 60J11		
	DATE - 12/20/2013	REVISED -						ILLINOIS FED. AID PROJECT				