


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	100% MWRD	100% RIVER FOREST WATERMAIN	100% ELMWOOD PARK WATERMAIN	100% ELMWOOD PARK EMERGENCY PRE-EMPTION	
				ROADWAY 0004	BRIDGE 0011	TRAFFIC SIGNALS 0021	UTILITY 0043	UTILITY 0043	UTILITY 0043	TRAFFIC SIGNALS 0021	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4							
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	5	5							
60250200	CATCH BASINS TO BE ADJUSTED	EACH	8	8							
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4							
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1							
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	4	4							
60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3							
60500040	REMOVING MANHOLES	EACH	4	4							
60500050	REMOVING CATCH BASINS	EACH	7	7							
60500060	REMOVING INLETS	EACH	2	2							
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1111	1111							
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1730	1730							
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	106	106							

* SPECIALTY ITEMS

 Bollinger, Lach & Associates, Inc. <small>PLANNING ENGINEERS ARCHITECTS</small> <small>CHICAGO, ILLINOIS</small>	USER NAME * USER#	DESIGNED - MTC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DESIGNED - MTC	REVISED -	307					541Y-3-B	COOK	143	11	
	FLAT SCALE * 4SCALE*	CHECKED - JIP	REVISED -					CONTRACT NO. 60J11				
	FLAT DATE * 4DATE*	DATE - 12/20/2013	REVISED -					ILLINOIS FED. AID PROJECT				
				SCALE: NONE			SHEET NO. 8 OF 18 SHEETS		STA. TO STA.			