

INLET FILTERS			
NO.	LOCATION STA.	OFFSET	QUANTITY (EACH)
IL ROUTE 64			
1	87+63.29	CL	1
2	88+88.99	CL	1
3	90+84.95	CL	1
4	89+20.42	LT	1
5	87+41.43	RT	1
6	89+68.74	RT	1
7	91+52.02	LT	1
8	92+00.00	LT	1
9	91+74.57	CL	1
10	91+95.17	RT	1
11	92+85.83	LT	1
12	92+90.16	RT	1
13	93+23.72	CL	1
14	94+10.25	LT	1
15	94+53.13	LT	1
16	95+30.00	LT	1
17	95+73.68	CL	1
18	95+30.31	RT	1
19	94+09.94	RT	1
20	96+90.19	RT	1
21	100+49.21	LT	1
22	100+56.33	LT	1
23	101+11.04	LT	1
24	101+21.80	LT	1
25	100+50.27	RT	1
26	101+11.76	RT	1
27	101+21.91	RT	1
28	102+69.95	LT	1
29	102+70.29	RT	1
30	96+89.94	LT	1
THATCHER AVE			
31	9+29.50	LT	1
32	9+19.12	LT	1
33	8+61.42	LT	1
34	9+05.48	RT	1
35	8+95.50	RT	1
36	8+63.54	RT	1
37	7+24.55	LT	1
38	7+32.73	RT	1
39	6+84.70	RT	1
40	6+96.60	RT	1
	TOTAL		40

LANDSCAPING PLACEMENT							
LOCATION STA. - STA.	OFFSET	TOPSOIL FURNISH AND PLACE 4" (SQ. YD.)	TOPSOIL FURNISH AND PLACE 6" (SQ. YD.)	COMPOST FURNISH AND PLACE 2" (SQ. YD.)	SEEDING, CLASS 2A (ACRE)	SEEDING, CLASS 4 (MODIFIED) (ACRE)	SODDING SALT TOLERANT (SQ. YD.)
IL ROUTE 64							
92+00.00 - 97+68.29	LT	1742			0.36		
92+00.00 - 97+68.29	RT	968			0.20		
97+68.29 - WATERS EDGE	LT		278	278		0.06	127
97+68.29 - WATERS EDGE	RT		206	206		0.04	
WATERS EDGE 99+75.00	LT		20	20		0.00	
WATERS EDGE 99+75.00	RT		98	98		0.02	
100+30.00 103+18.00	RT	130					
THATCHER AVE							
6+25.00 - 7+30.00	LT	72					72
8+48.00 - 9+75.00	LT	97					97
6+25.00 - 7+16.00	RT	35					35
	TOTAL	3044	602	602	0.56	0.12	331

PROPOSED PAVEMENT MARKING						
LOCATION STA. - STA.	EPOXY PAVEMENT					
	MARKING LINE				LETTERS & SYMBOLS (SQ FT)	
	4" (FT)	6" (FT)	12" (FT)	24" (FT)		
IL ROUTE 64						
92+00.00 - 100+00.00	2940	698	84	50	177	
100+00.00 - 104+00.00	1028	840	100	48	36	
THATCHER AVE						
2+50.00 - 7+50.00	980	287	90	---	73	
7+50.00 - 13+00.00	1870	434	50	62	73	
	TOTAL	6818	2259	324	160	359

FILE NAME = \$FILEL\$

**B** Bollinger, Lach & Associates, Inc.  
ITASCA, ILLINOIS

USER NAME = \$USER*	DESIGNED - MTC	REVISED -
	DRAWN - MTC	REVISED -
PLOT SCALE = \$SCALE*	CHECKED - JIP	REVISED -
PLOT DATE = \$DATE*	DATE - 12/20/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER  
SCHEDULE OF QUANTITIES**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	541Y-3-B	COOK	143	18
CONTRACT NO. 60J11				
ILLINOIS FED. AID PROJECT				

SCALE: NONE SHEET NO. 4 OF 4 SHEETS STA. TO STA.