



THE CONTRACTOR SHALL CONTACT THE ROADSIDE DEVELOPMENT UNIT, MELISSA DEL ROSARIO AT 847-705-4397, PRIOR TO THE START OF CONSTRUCTION TO COORDINATE THE LOCATION OF THE SELECTIVE TREES TO BE REMOVED.

- DRIVEWAY REMOVAL
- PAVEMENT REMOVAL
- TREE REMOVAL

NOTE: REMOVALS OF EXISTING STORM SEWER AND STORM STRUCTURES IS SHOWN ON THE DRAINAGE PLAN AND UTILITIES SHEETS, SEE DRAINAGE PLAN AND UTILITIES SHEETS.

EXISTING GUARDRAIL AND TERMINAL BARRIERS TO BE REMOVED AS SHOWN ON THE PLANS SHALL BE PAID FOR AS "GUARDRAIL REMOVAL"

EXISTING MULTI-USE PATH REMOVAL SHALL BE PAID FOR AS "PAVEMENT REMOVAL"

FILE NAME = \$FILEL\$



USER NAME = \$USER\$	DESIGNED - MTC	REVISED -
PLOT SCALE = \$SCALE\$	DRAWN - MTC	REVISED -
PLOT DATE = \$DATE\$	CHECKED - JIP	REVISED -
	DATE - 12/20/2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 64 (NORTH AVE) OVER THE DES PLAINES RIVER  
REMOVAL PLAN**

SCALE: 1"=50'      SHEET NO. 1 OF 1 SHEETS      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
307	541Y-3-B	COOK	143	20
CONTRACT NO. 60J11				
ILLINOIS FED. AID PROJECT				