

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QTY	90% FED. / 10% STATE															
				90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	90% FED. 10% STATE	100% VILL. OF UNIV. PARK	90% FED. 10% STATE	CULVERT UNDER STUENKEL RD	CULVERT UNDER RAMP B/ I-57/RAMP D	CULVERT UNDER RAMP A							
				ROADWAY	SAFETY	LIGHTING	SIGNAL	BRIDGE	0011	0011	0011	0011							
				0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	SN-099-0526	SN-099-6010	SN-099-0608	SN-099-0609							
81300000	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 12" X 6"	EACH	2			2													
81304600	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"	EACH	6			4		2											
81400100	HANDHOLE	EACH	14	▲				14	▲										
81400200	HEAVY-DUTY HANDHOLE	EACH	3					3											
81400300	DOUBLE HANDHOLE	EACH	3	▲				3	▲										
81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	2447			2447													
81603081	UNIT DUCT, 600V, 3-1C NO.2, 1/C NO.4 GROUND, (XLP-TYPE USE), 1 1/2" DIA. POLYETHYLENE	FOOT	26,750			26,750													
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	3120			3120													
81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	570			570													
81702220	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C 350MCM	FOOT	150			150													
81702400	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 2	FOOT	1785			1785													
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	700			700													
81800290	AERIAL CABLE, 3-1/C NO.1/0, WITH MESSENGER WIRE	FOOT	480			480													
81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	12,750			12,750													
82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	88			88													

• SPECIALTY ITEM

▲ Rev. 1-9-14

Rev.

TYLIN INTERNATIONAL	USER NAME	DESIGNED - JTP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STUENKEL ROAD AT I-57 RIDGELAND AVENUE TO CENTRAL AVENUE SUMMARY OF QUANTITIES	F.A.I. R.E.E.	SECTION	COUNTY	TOTAL SHEETS	
	PLG3	DRAWN - JTP	REVISED -			ST	99-IHB-RI	WILL	679	19
	PLG2	CHECKED - JPM	REVISED -			CONTRACT NO. 60L69				
	PLG1	DATE - 05/10/2013	REVISED -			ILLINOIS FED. AID PROJECT				

SCALE: N.T.S. SHEET 16 OF 24 SHEETS STA. TO STA.