

EXISTING SIGN SCHEDULE

SIGN NO.	ALIGNMENT	EX. STATION	OFFSET	REMOVE SIGN PANEL ASSEMBLY	RELOCATE SIGN PANEL ASSEMBLY	PROP. STATION	OFFSET	SIGN PANEL				SUPPORT INFORMATION			SIGN DESIGNATION	SIGN DESCRIPTION
								TYPE	WIDTH (FT)	HEIGHT (FT)	AREA (SQ FT)	TYPE	POST QUANTITY	TOTAL POST LENGTH (FT)		
1	EB STUENKEL ROAD	16003+07.00	22.5 RT		1	16002+63.00	50.00 RT	1	3	3	9	METAL	1	9.0	R1-1	STOP
2	EB STUENKEL ROAD	SAME AS ABOVE				SAME AS ABOVE			1.5	0.5	0.75	-			R1-3P	ALL WAY (PLAQUE)
3	STUENKEL & RIDGELAND	16003+17.21	28.37 LT	1				1	2.5	0.5	1.25	METAL	1	9.0	D3-1	STUENKEL RD
4	STUENKEL & RIDGELAND	SAME AS ABOVE							2.5	0.5	1.25	-			D3-1	RIDGELAND AVE
5	WB STUENKEL ROAD	16003+83.31	17.87 LT	1				1	2.5	2.5	6.25	METAL	1	9.0	R1-1	STOP
6	WB STUENKEL ROAD	SAME AS ABOVE							2	1	2	-			W4-4P	CROSS TRAFFIC DOES NOT STOP
7	WB STUENKEL ROAD	16004+47.93	21.25 RT	1				1	2.5	2.5	6.25	METAL	1	9.0	CUSTOM WARNING	ROAD CLOSED
8	WB STUENKEL ROAD	16050+00.00	20.00 LT	1				1	1	1.5	1.5	METAL	1	9.0	R2-1	SPEED LIMIT
9	EB STUENKEL ROAD	16054+33.34	13.46 LT	1				1	2	2.5	5	METAL	1	9.0		NO DUMPING
10	EB STUENKEL ROAD	16055+72.47	29.22 LT	1				1	2	2.5	5	METAL	1	9.0	R12-1	WEIGHT LIMIT
11	EB STUENKEL ROAD	16056+86.83	39.46 LT	1				1	3	3	9	METAL	1	9.0		CUSTOM INFO SIGN
12	WB STUENKEL ROAD	16056+93.41	30.45 LT	1				1	3	3	9	METAL	1	9.0	R1-1	STOP
13	WB STUENKEL ROAD	SAME AS ABOVE							1.5	0.5	0.75	-			R1-3P	ALL WAY (PLAQUE)
14	EB STUENKEL ROAD	16057+50.06	27.31 RT	1				1	2	2	4	METAL	1	9.0	R5-2	NO TRUCKS
15	NB CENTRAL AVE	799+39.50	60.70 RT	1				1	3	3	9	METAL	1	9.0	R1-1	STOP
16	NB CENTRAL AVE	SAME AS ABOVE							1.5	0.5	0.75	-			R1-3P	ALL WAY (PLAQUE)
17	SB CENTRAL AVE	800+53.92	35.00 RT	1				1	3	3	9	METAL	1	9.0	R1-1	STOP
18	SB CENTRAL AVE	SAME AS ABOVE							1.5	0.5	0.75	-			R1-3P	ALL WAY (PLAQUE)
19	SB CENTRAL AVE	795+98.82	25.80 LT	1				1	2	2	4	METAL	1	9.0	R2-1	SPEED LIMIT
20	NB CENTRAL AVE	798+34.06	30.71 RT	1				1	2.5	2.5	6.25	METAL	1	9.0	R3-7	LEFT LANE TURN
21	SB CENTRAL AVE	803+58.26	27.66 LT	1				1	2.5	2.5	6.25	METAL	1	9.0	W3-1	STOP AHEAD
22	SB I-57	1294+36.50	80.00 RT	1				3	12	8	96	*W6X15	2	46.0	INFORMATIONAL SIGN	GOVERNORS STATE UNIVERSITY
23	SB I-57	1435+98.00	96.00 LT		1	1395+00.00	80.00 LT	3	12	8	96	*W6X15	2	46.0	SPECIFIC SERVICE SIGN	GAS - EXIT 335
24	SB I-57	1445+86.00	104.00 LT		1	1403+00.00	80.00 LT	3	16	12	192	*W10X22	3	84.0	SPECIFIC SERVICE SIGN	FOOD - EXIT 335
25	NB I-57	1454+00.00	95.00 RT		1	1454+00.00	110.00 RT	2	6	2	12	WOOD	2	20.0	CUSTOM NAME	STUENKEL RD
26	SB I-57	1455+70.83	93.83 LT		1	1456+04.00	90.00 LT	2	5	4	20	WOOD	2	24.0	CUSTOM NAME	STUENKEL RD
27	SB I-57	1462+96.00	93.00 LT		1	1411+00.00	80.00 LT	3	12	12	144	*W8X18	2	55.0	SPECIFIC SERVICE SIGN	LODGING - EXIT 335
28	SB I-57	1577+83.00	80.00 LT		1			3	12	8	96	*W6X15	2	46.0	INFORMATIONAL SIGN	GOVERNORS STATE UNIVERSITY
				TOTAL:	16	6										

\*EXISTING SIGN DIMENSIONS HAVE BEEN VISUALLY SURVEYED AND NEED TO BE VERIFIED. SUPPORT TYPE AND FOUNDATION QUANTITIES NEED TO BE RECALCULATED BY ENGINEER IF VERIFIED DIMENSIONS DIFFER.

ADDITIONAL EXISTING SIGNS HAVE BEEN OBSERVED, BUT NOT SURVEYED, WITHIN THE PROPOSED RIGHT OF WAY. THE CONTRACTOR SHOULD COORDINATE REMOVAL/REPLACEMENT WITH THE OWNING ENTITY. WORK SHALL BE PAID FOR AS "RELOCATE SIGN PANEL ASSEMBLY-TYPE B".