



SCHEDULE OF INTERCONNECT QUANTITIES

QUANTITY	UNIT	ITEM
958	FOOT	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.
50	FOOT	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC
2	EACH	JUNCTION BOX EMBEDDED IN STRUCTURE 18" X 12" X 6"
2	EACH	HANDHOLE
1	EACH	MASTER CONTROLLER
1878	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER NO. 14 1C
1904	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F
1	EACH	OPTIMIZE TRAFFIC SIGNAL SYSTEM

J:\27\06\1\CA00_Sheets\BOLC69-sh1-t5-17.dgn
 26-DEC-2013 14:57



USER NAME * kpra_jopati	DESIGNED - MG	REVISED Δ - ADDENDUM I 1/03/14
PLOT SCALE * 48.000000in.000000	DRAWN - MG	REVISED -
PLOT DATE * 26-DEC-2013 14:57	CHECKED - KGP/VO	REVISED -
	DATE - 05/09/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INTERCONNECT SCHEMATIC STUENKEL ROAD FROM I-57 WEST RAMP TO I-57 EAST RAMP		F.A.I. RTE. 57	SECTION 99-INB-R	COUNTY WILL	TOTAL SHEETS 679	SHEET NO. 322
SCALE: AS NOTED		SHEET NO. 17 OF 18 SHEETS		STA. TO STA.		ILLINOIS FED. AID PROJECT CONTRACT NO. 60L69

ENTIRE SHEET REVISED