ORIGINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED — BY — DATE — NOTE: KNOW

FINAL SURVEY — SURVEYED / PLOTTED / TEMPLATE / AREAS / AREAS CHECKED — BY — DATE — NO.

TYLIN INTERNATIONAL

NO.	DATE	REVISION	BY
1	5/10/2011	ADDED STA. 505+00.00 TO STA. 506+00.00	JSP
2	5/12/2011	ADDED STA. 505+50.00	JSP
3	5/25/2011	ADDED STA. 505+00.00	JSP

DESIGNED JSP — DRAWN JSP — CHECKED PM — DATE 5/10/2011

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

I-57 AT STUENKEL ROAD (NEW INTERCHANGE)
PROPOSED RAMP E CROSS SECTIONS

SCALES: 1" = 5' H, 1" = 5' V — SHEET NO. 9 OF 9 SHEETS — STA. 506+00.00 TO STA. 504+00.00

F.A.I. RTE. 57 — SECTION 99(108)RI — COUNTY WILLIAMSON — CONTRACT NO. 60L69

PROPOSED @ RAMP E

STA.506+00.00

QUANTITIES (SF)
EXCAVATION = 0.0
UNSUITABLE = 126.0
EMBANKMENT = 642.2
TOPSOIL = 86.3

506+00.00 — 764.76 — 2.0% — 6.0% — 1:4 — 1:3 — 755.00

WATCH INC WEST DETENTION POND GRADING

PROPOSED 30" STORM SEWER

INV. 752.63

PROPOSED R.O.W. & ACCESS CONTROL

PROPOSED @ RAMP E

STA.505+50.00

QUANTITIES (SF)
EXCAVATION = 0.0
UNSUITABLE = 111.8
EMBANKMENT = 637.0
TOPSOIL = 72.1

505+50.00 — 764.96 — 2.0% — 6.0% — 1:4 — 1:3 — 754.95

WATCH INC WEST DETENTION POND GRADING

PROPOSED R.O.W. & ACCESS CONTROL

PROPOSED @ RAMP E

STA.505+00.00

QUANTITIES (SF)
EXCAVATION = 0.0
UNSUITABLE = 114.0
EMBANKMENT = 695.3
TOPSOIL = 74.1

505+00.00 — 765.9 — 2.0% — 6.0% — 1:4 — 1:3 — 754.89

WATCH INC WEST DETENTION POND GRADING

PROPOSED R.O.W. & ACCESS CONTROL

90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90

775 770 765 760 755 750 745