

CONSTRUCTION CODES

URBAN

80% FED. / 10% STATE

SP	SI	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	TRAINEES
						0004	0014	0042
		50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1	
		50102400	CONCRETE REMOVAL	CU YD	19.2		19.2	
		50200100	STRUCTURE EXCAVATION	CU YD	11		11	
		50300225	CONCRETE STRUCTURES	CU YD	107		107	
		50300255	CONCRETE SUPERSTRUCTURE	CU YD	117.8		117.8	
		50300260	BRIDGE DECK GROOVING	SO YD	1191		1191	
		50300300	PROTECTIVE COAT	SO YD	2309	462	1847	
		50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SO FT	9427		9427	
		50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	20420		20420	
		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	48,130		48,130	
		50800515	BAR SPLICERS	EACH	279		279	
		50901720	BICYCLE RAILING	FOOT	457	76	381	
		50901750	PARAPET RAILING	FOOT	381		381	
		51500100	NAME PLATES	EACH	1		1	

14

• SPECIALTY ITEM  
X SPECIAL PROVISION ITEM

ILL 132 over DesPlaines River-12-154-081A-DRAINAGE-603 Sheets-DIL132-1st-500.dgn



USER NAME = KyleC  
 PLOT SCALE =  
 PLOT DATE = 9/3/2013

DESIGNED - HTC  
 DRAWN - HTC  
 CHECKED - DPA  
 DATE - 09/03/13

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

IL 132 (GRAND AVE.) OVER DES PLAINES RIVER  
 SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 4 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
541	X-6-B-1-1	LAKE	93	8
ILLINOIS FED. AID PROJECT			CONTRACT NO. 60N22	

Rev.