



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 19, 2014

SUBJECT: FAU Route 3887 (IL 31)  
Project ACHPP-ACM-3887(009)  
Section 18W & RS-5 (12)  
McHenry County  
Contract No. 60V72  
Item No. 116, February 28, 2014 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page 3 & 4 of the Special Provisions, revising the Completion Date
3. Revised sheets 7, 8, 10 & 56 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; D. Carl Puzey; Estimates

MS/kf

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
ACHPP-ACM-3887/009/

Route  
FAU 3887

County Name - MCHENRY- -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000120	T-ACERX FREM AB 2-1/2	EACH	6.000				
A2002376	T-BETULA NIGRA CL 12'	EACH	6.000				
A2006270	T-POPUL TREM CL 8'	EACH	6.000				
A2006516	T-QUERCUS BICOL 2	EACH	1.000				
A2008416	T-TILIA TOM STR 2	EACH	2.000				
B0001720	T-AMEL X GF AP SF 12'	EACH	5.000				
B2000123	T-A TATRM JFS-KW2 2TF	EACH	14.000				
B2001168	T-CERCIS CAN CL 7'	EACH	6.000				
B2003416	T-MALUS FLOR TF 2	EACH	11.000				
B2006126	T-SYRG P ZHING 2-1/2	EACH	9.000				
C2C09624	S-SAMBUCUS CANAD 2'C	EACH	90.000				
C2002948	S-FORSYTH X INT 4'	EACH	11.000				
C2011748	S-VIBURN DENT 4'	EACH	44.000				
D2C00424	E-JUNIP CH PFITZ 2'C	EACH	9.000				
XX004913	REMOV FOC FR CONDUIT	FOOT	4,100.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
XX006821	CONC TRUCK WASHOUT	L SUM	1.000				
XZ127900	RETAINING WALL REMOV	FOOT	65.000				
X0320239	CONC WALL REMOV	FOOT	302.000				
X0322936	REMOV EX FLAR END SEC	EACH	12.000				
X0323360	WOOD POLE REMOVAL	EACH	1.000				
X0323443	PREC MOD RET WALL	SQ FT	847.000				
X0325034	MH TA 6D W/2 T1FOL RP	EACH	8.000				
X0325938	TEMP WIR INTERCON COM	L SUM	1.000				
X0326864	BRICK SIDEWALK REM	SQ FT	114.000				
X0327009	REMOVE SIGN SPECIAL	EACH	3.000				
X0327032	TEMP VIDEO DETECTION	EACH	1.000				
X0327037	SPECIAL GRATE NO. 1	EACH	1.000				
X0327301	RELOCATE EX MAILBOX	EACH	9.000				
X2130010	EXPLOR TRENCH SPL	FOOT	200.000				
X4021000	TEMP ACCESS- PRIV ENT	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X4022000	TEMP ACCESS- COM ENT	EACH	11.000				
X6640300	CH LK FENCE REMOV	FOOT	34.000				
X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
*REV X7030025	WET REF TEM TP T3 L&S	SQ FT	146.000				
*REV X7030030	WET REF TEM TAPE T3 4	FOOT	34,350.000				
X7030040	WET REF TEM TAPE T3 6	FOOT	1,358.000				
X7030050	WET REF TEM TPE T3 12	FOOT	1,514.000				
X7030055	WET REF TEM TPE T3 24	FOOT	109.000				
X8710024	FOCC62.5/125 MM12SM24	FOOT	7,476.000				
Z0004530	HMA DRIVEWAY PAVT 8	SQ YD	214.000				
Z0004538	HMA DRIVEWAY PAVT 10	SQ YD	1,035.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0019600	DUST CONTROL WATERING	UNIT	2,880.000				
Z0022800	FENCE REMOVAL	FOOT	245.000				
Z0030850	TEMP INFO SIGNING	SQ FT	75.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0046304	P UNDR FOR STRUCT 4	FOOT	160.000				
Z0062456	TEMP PAVEMENT	SQ YD	1,085.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	1.000				
Z0076600	TRAINEES	HOUR	1,500.000		0.800		1,200.000
Z0076604	TRAINEES TPG	HOUR	1,500.000		15.000		22,500.000
20100110	TREE REMOV 6-15	UNIT	1,315.000				
20100210	TREE REMOV OVER 15	UNIT	307.000				
20100500	TREE REMOV ACRES	ACRE	0.700				
20101700	SUPPLE WATERING	UNIT	3.000				
20200100	EARTH EXCAVATION	CU YD	11,625.000				
20201200	REM & DISP UNS MATL	CU YD	865.000				
20400800	FURNISHED EXCAVATION	CU YD	32,425.000				
20800150	TRENCH BACKFILL	CU YD	3,605.000				
21001000	GEOTECH FAB F/GR STAB	SQ YD	6,311.000				
21101615	TOPSOIL F & P 4	SQ YD	28,606.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY- -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
21101685	TOPSOIL F & P 24	SQ YD	3,918.000				
25000210	SEEDING CL 2A	ACRE	5.500				
25000310	SEEDING CL 4	ACRE	0.250				
25000400	NITROGEN FERT NUTR	POUND	415.000				
25000500	PHOSPHORUS FERT NUTR	POUND	415.000				
25000600	POTASSIUM FERT NUTR	POUND	415.000				
25100630	EROSION CONTR BLANKET	SQ YD	28,008.000				
25200110	SODDING SALT TOLERANT	SQ YD	5,700.000				
28000250	TEMP EROS CONTR SEED	POUND	580.000				
28000305	TEMP DITCH CHECKS	FOOT	934.000				
28000400	PERIMETER EROS BAR	FOOT	5,578.000				
28000510	INLET FILTERS	EACH	82.000				
30300001	AGG SUBGRADE IMPROVE	CU YD	6,083.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	32,334.000				
31101400	SUB GRAN MAT B 6	SQ YD	5,243.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY--

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
40600300	AGG PR CT	TON	7.500				
40603335	HMA SC "D" N50	TON	380.000				
42000501	PCC PVT 10 JOINTED	SQ YD	26,474.000				
42001300	PROTECTIVE COAT	SQ YD	32,036.000				
44000100	PAVEMENT REM	SQ YD	17,259.000				
44000200	DRIVE PAVEMENT REM	SQ YD	1,157.000				
44000300	CURB REM	FOOT	411.000				
44000500	COMB CURB GUTTER REM	FOOT	268.000				
44000600	SIDEWALK REM	SQ FT	601.000				
44003100	MEDIAN REMOVAL	SQ FT	1,809.000				
44004250	PAVED SHLD REMOVAL	SQ YD	8,373.000				
44201769	CL D PATCH T3 10	SQ YD	46.000				
44201771	CL D PATCH T4 10	SQ YD	338.000				
50105220	PIPE CULVERT REMOV	FOOT	344.000				
542A0220	P CUL CL A 1 15	FOOT	337.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A0223	P CUL CL A 1 18	FOOT	47.000				
542A0229	P CUL CL A 1 24	FOOT	145.000				
542A1909	P CUL CL A 3 24	FOOT	194.000				
54213657	PRC FLAR END SEC 12	EACH	2.000				
54213660	PRC FLAR END SEC 15	EACH	20.000				
54213663	PRC FLAR END SEC 18	EACH	6.000				
54213666	PRC FLAR END SEC 21	EACH	2.000				
54213669	PRC FLAR END SEC 24	EACH	6.000				
550A0050	STORM SEW CL A 1 12	FOOT	1,415.000				
550A0070	STORM SEW CL A 1 15	FOOT	634.000				
550A0090	STORM SEW CL A 1 18	FOOT	101.000				
550A0110	STORM SEW CL A 1 21	FOOT	56.000				
550A0120	STORM SEW CL A 1 24	FOOT	289.000				
550A0160	STORM SEW CL A 1 36	FOOT	112.000				
550A0340	STORM SEW CL A 2 12	FOOT	321.000				



ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

County Name - MCHENRY- -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
550A0380	STORM SEW CL A 2 18	FOOT	300.000				
550A0410	STORM SEW CL A 2 24	FOOT	201.000				
550A0450	STORM SEW CL A 2 36	FOOT	1,318.000				
550A4300	SS CL A 1 EQRS 30	FOOT	457.000				
550A5100	SS CL A 2 EQRS 30	FOOT	274.000				
550B0330	STORM SEW CL B 2 10	FOOT	36.000				
55100900	STORM SEWER REM 18	FOOT	310.000				
55101100	STORM SEWER REM 21	FOOT	154.000				
55101200	STORM SEWER REM 24	FOOT	77.000				
60107600	PIPE UNDERDRAINS 4	FOOT	948.000				
60201340	CB TA 4 DIA T24F&G	EACH	37.000				
60205040	CB TA 5 DIA T24F&G	EACH	1.000				
60208240	CB TC T24F&G	EACH	32.000				
60218400	MAN TA 4 DIA T1F CL	EACH	13.000				
60219540	MAN TA 4 DIA T24F&G	EACH	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY- -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60221100	MAN TA 5 DIA T1F CL	EACH	15.000				
60222240	MAN TA 5 DIA T24F&G	EACH	1.000				
60224446	MAN TA 7 DIA T1F CL	EACH	2.000				
60240328	INLETS TB T24F&G	EACH	7.000				
60500050	REMOV CATCH BAS	EACH	2.000				
60600605	CONC CURB TB	FOOT	210.000				
60605000	COMB CC&G TB6.24	FOOT	12,736.000				
60618300	CONC MEDIAN SURF 4	SQ FT	1,251.000				
60619600	CONC MED TSB6.12	SQ FT	10,476.000				
66700305	PERM SURV MKRS T2	EACH	1.000				
66900200	NON SPL WASTE DISPOSL	CU YD	7,200.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	5.000				
*REV 67000400	ENGR FIELD OFFICE A	CAL MO	16.000				
67100100	MOBILIZATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100450	TRAF CONT-PROT 701201	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
*REV 70106800	CHANGEABLE MESSAGE SN	CAL MO	24.000				
70300220	TEMP PVT MK LINE 4	FOOT	13,714.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	10,131.000				
70400100	TEMP CONC BARRIER	FOOT	4,604.000				
70600250	IMP ATTN TEMP NRD TL3	EACH	2.000				
70600260	IMP ATTN TEMP FRN TL3	EACH	1.000				
72000100	SIGN PANEL T1	SQ FT	125.000				
72400100	REMOV SIN PAN ASSY TA	EACH	15.000				
72400500	RELOC SIN PAN ASSY TA	EACH	4.000				
72400600	RELOC SIN PAN ASSY TB	EACH	1.000				
72800100	TELES STL SIN SUPPORT	FOOT	418.000				
78008200	POLYUREA PM T1 LTR-SY	SQ FT	633.000				
78008210	POLYUREA PM T1 LN 4	FOOT	2,507.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60V72

State Job # - C-91-062-13

Project Number  
 ACHPP-ACM-3887/009/

Route  
 FAU 3887

County Name - MCHENRY - -

Code - 111 - -

District - 1 - -

Section Number - 18W&RS-5 (12)

\*REVISED: FEBRUARY 18, 2014

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008230	POLYUREA PM T1 LN 6	FOOT	4,550.000				
78008250	POLYUREA PM T1 LN 12	FOOT	729.000				
78008270	POLYUREA PM T1 LN 24	FOOT	39.000				
78100100	RAISED REFL PAVT MKR	EACH	305.000				
78300100	PAVT MARKING REMOVAL	SQ FT	5,413.000				
81028200	UNDRGRD C GALVS 2	FOOT	3,434.000				
81400100	HANDHOLE	EACH	8.000				
81400200	HD HANDHOLE	EACH	1.000				
85000200	MAIN EX TR SIG INSTAL	EACH	2.000				
87300925	ELCBL C TRACER 14 1C	FOOT	7,453.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	139.000				
87900200	DRILL EX HANDHOLE	EACH	3.000				
88600100	DET LOOP T1	FOOT	52.000				
89502300	REM ELCBL FR CON	FOOT	4,077.000				
89502380	REMOV EX HANDHOLE	EACH	7.000				

<u>Name of Utility</u>	<u>Type</u>	<u>Location</u>	<u>Estimated Dates for Start and Completion of Relocation or Adjustments</u>
NICOR Gas Constance Lane 1844 Ferry Road Naperville, IL 60583 (630)388-3830	Underground Lines	West side of IL 31 from Sta. 279+00 to 282+75 (Approx)	This work is scheduled to be completed prior to construction
Commonwealth Edison Robert Hauser 123 Energy Avenue Rockford, IL 61109 (815) 490-2231	Poles & Overhead Lines	West side of IL 31	Existing overhead lines will be relocated to new pole locations. This work is scheduled to start prior to construction.
Comcast Thomas Munar 688 Industrial Drive Elmhurst, IL 60126 (630)600-6316	Overhead Lines	West side of IL 31 (all lines are on ComEd poles)	Existing overhead lines will be relocated to new pole locations. This work is scheduled to start prior to construction.
AT&T David Saint Germain 255 East Chicago St. Elgin, IL 60120 (815)394-7297	Underground Lines, Ducts and Vaults	West side of IL 31	Main ducts are scheduled to be installed prior to construction. Vaults are scheduled during construction.

The above represents the best information available to the Department and is included for the convenience of the bidder. The applicable portions of Articles 105.07 and 107.31 of the Standard Specifications shall apply.

In accordance with 605 ILCS 5/9-113 of the Illinois Compiled Statutes, utility companies have 90 days to complete the relocation of their facilities after receipt of written notice from the Department. The 90-day written notice will be sent to the utility companies after the following occurs:

- 1) Proposed right of way is clear for contract award.
- 2) Final plans have been sent to and received by the utility company.
- 3) Utility permit is received by the Department and the Department is ready to issue said permit.
- 4) If a permit has not been submitted, a 15 day letter is sent to the utility company notifying them they have 15 days to provide their permit application. After allowing 15 days for submission of the permit the 90 day notice is sent to the utility company.
- 5) Any time within the 90 day relocation period the utility company may request a waiver for additional time to complete their relocation. The Department has 10 days to review and respond to a waiver request.

**COMPLETION DATE PLUS WORKING DAYS**

Effective: September 30, 1985

Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on May 15, 2015 except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within 5 working days after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

**EMBANKMENT I**

Effective: March 1, 2011

Description. This work shall be according to Section 205 of the Standard Specifications except for the following.

Material. All material shall be approved by the District Geotechnical Engineer. The proposed material must meet the following requirements.

- a) The laboratory Standard Dry Density shall be a minimum of 90 lb/cu ft (1450 kg/cu m) when determined according to AASHTO T 99 (Method C).
- b) The organic content shall be less than ten percent determined according to AASHTO T 194 (Wet Combustion).
- c) Soils which demonstrate the following properties shall be restricted to the interior of the embankment and shall be covered on both the sides and top of the embankment by a minimum of 3 ft (900 mm) of soil not considered detrimental in terms of erosion potential or excess volume change.
  - 1) A grain size distribution with less than 35 percent passing the number 75 um (#200) sieve.
  - 2) A plasticity index (PI) of less than 12.

Revised 2/19/14