

LOCATION	1				2				3			4				5			
STRUCTURE NUMBER	016-0014				016-0015				016-0991			016-0158				016-0159			
	# OF TIMBERS	INDIVIDUAL LENGTH OF TIMBERS	TOTAL LENGTH - FEET	TOTAL LENGTH - F.B.M.	# OF TIMBERS	INDIVIDUAL LENGTH OF TIMBERS	TOTAL LENGTH - FEET	TOTAL LENGTH - F.B.M.	NORTH BASCULE	SOUTH BASCULE	TOTAL	# OF TIMBERS	INDIVIDUAL LENGTH OF TIMBERS	TOTAL LENGTH - FEET	TOTAL LENGTH - F.B.M.	# OF TIMBERS	INDIVIDUAL LENGTH OF TIMBERS	TOTAL LENGTH - FEET	TOTAL LENGTH - F.B.M.
8x12 TIMBER UNDERWATER	*4	18'-10"	75.33'		*0	18'-10"	0'												
	12	13'-11"	167'		12	13'-11"	167'												
	8	18'-4"	146.7'		8	18'-4"	146.7'												
	4	17'-10"	71.3'		4	17'-10"	71.3'												
TOTAL			460.3'	3683			385'	3080											
6x12 TIMBER UNDERWATER	14	2'-0"	28'		30	2'-0"	60'					7	12'-8"	88.7'		1	12'-8"	12.67'	
												1	16'-0"	16'					
												1	10'-10"	10'					
												2	22'-6"	45'					
TOTAL			28'	168			60'	360						159.7	959			12.67'	77
STRUCTURAL REPAIR OF CONCRETE < OR = TO 5"									2 SF	1 SF	3 SF								
STRUCTURAL REPAIR OF CONCRETE > 5"									2 SF	0 SF	2 SF								
EPOXY CRACK INJECTION									14 FT	0 FT	14 FT								
6x12 TIMBER												2	12'-8"	25.33'	152	4	12'-8"	50.67'	305
4"x8"x1" TIMBER												7	1'-0"	7'	19	9	1'-0"	9'	24
4"x8"x1" TIMBER UNDERWATER												19	1'-0"	19'	51	3	1'-0"	3'	8

NOTE: TIMBERS THAT SPAN BETWEEN STRUCTURES 016-0014 AND 016-0015 HAVE BEEN CONSOLIDATED, AND ARE ACCOUNTED FOR UNDER ' OF TIMBERS' FOR S.N. 016-0014.

FILE NAME =	USER NAME = hardnetbr	DESIGNED - BH, RA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
en:\p\work\p\dot\hardnetbr\0359751\041113-whi-plan.dgn	DRAWN - 11/20/13	REVISED -	VAR.						2013-043BR	COOK	22	4	
PLOT SCALE = 100.0000' / 1"	CHECKED - JAM	REVISED -	CONTRACT NO. 60W97										
Default	DATE - 11/21/13	REVISED -	ILLINOIS FED. AID PROJECT										