

DATE		BY	
PROFILE		STRUCTURE	
NOTED		NOTATED	
CHECKED		CHECKED	
DATE		DATE	
BY		BY	
DATE		DATE	
BY		BY	
DATE		DATE	

**CHRISTOPHER B. BURKE**  
 ENGINEERING LTD.  
 9575 Wood Highway Road, Suite 600  
 Rosemont, Illinois 60018  
 (647) 825-5000

**C B**

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	IL ROUTE 50 AT SOUTHWEST HIGHWAY			INTERCONNECT
				CONSTRUCTION CODE			
				0005	0021	0021	0021
				HSIP FUNDS 90% FED 10% STATE	HSIP FUNDS 90% FED 10% STATE	LOCAL FUNDS 100% LOCAL	HSIP FUNDS 90% FED 10% STATE
			<i>URBAN</i>				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	7	7			
20700220	POROUS GRANULAR EMBANKMENT	CU YD	7	7			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	20	20			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	325	325			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6	6			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6	6			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6	6			
<del>25200100</del>	<del>SODDING</del>	<del>SQ YD</del>	<del>325</del>	<del>325</del>			
25200110	SODDING, SALT TOLERANT	SQ YD	325	325			
25200200	SUPPLEMENTAL WATERING	UNIT	1	1			
28000510	INLET FILTERS	EACH	10	10			
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	713	713			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	330	330			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	75	75			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	30	30			

\* SPECIALITY ITEM

FILE NAME :	USER NAME :	DESIGNED :	REVISED :	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.R. RTE. 350 SECTION 461TS-2(13) COUNTY COOK TOTAL SHEETS 42 SHEET NO. 3
DATE:	DATE:	DRAWN :	REVISED :		SHEET 1 OF 7			
PLOT SCALE :	PLOT SCALE :	CHECKED :	REVISED :		SCALE: _____ SHEET NO. _____ OF _____ SHEETS			
PLOT DATE :	PLOT DATE :	DATE :	REVISED :		STA. _____ TO STA. _____			

CONTRACT NO. 60X25

ILLINOIS FED. AID PROJECT

*Rev.*