

CODE NO	ITEM	UNIT	ALDEN	CRYSTAL LAKE	HEBRON		MARENGO	McHENRY	RICHMOND	WOODSTOCK	TOTAL
			IL173	IL 176	IL 173	IL 47	IL 23	IL 31	US 12	IL 47	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	0.00	15.03	2.91	7.83	6.73	7.42	9.46	10.75	60
20400800	FURNISHED EXCAVATION	CU YD	0.00	4.16	1.84	5.00	0.86	0.00	2.64	0.41	15
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	10	338	122	99.6	71	40	57	81	819
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	0	4	2	1	1	0	1	1	10
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	0	4	2	1	1	0	1	1	10
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	0	4	2	1	1	0	1	1	10
25200110	SODDING, SALT TOLERANT	SQ YD	10	338	122	100	71	40	57	81	819
25200200	SUPPLEMENTAL WATERING	UNIT	0	3	1	1	1	0	1	1	8
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	0.00	1.84	2.86	0.00	0.00	0.00	0.42	0.00	5
42001300	PROTECTIVE COAT	SQ YD	32	525	176	204	287	77	185	229	1715
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	287	3407	1472	1062	1733	389	1132	1052	10533
42400800	DETECTABLE WARNINGS	SQ FT	103	311	127	201	157	43	107	138	1187
44000600	SIDEWALK REMOVAL	SQ FT	255	3404	1437	1514	1670	615	1044	1006	10945
44002206	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 1 1/2"	SQ YD	0	22	4	2	0	0	1	0	28
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	0	22	4	0	0	0	1	0	26
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJ	EACH	0	0	0	0	1	0	1	0	2
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	0	5	1	2	5	0	0	1	14
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	0	5	0	1	0	1	1	2	10
60300405	VALVE BOX FRAMES TO BE ADJUSTED	EACH	0	1	0	0	0	0	0	0	1
60404950	FRAMES AND GRATES, TYPE 24	EACH	0	1	0	0	0	0	0	0	1
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	0	4	1	2	1	1	0	2	11
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	0	4	1	2	1	1	0	2	11
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	0	0	30	0	0	0	0	20	50
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	365	692	407	561	300	197	667	107	3296
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	0	60	0	258	174	329	0	489	1309
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	64	96	20	101	83	0	48	171	583
78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	0	0	0	0	294	0	0	0	294
78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	0	0	0	0	44	32	0	0	76
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	0	4	0	0	0	0	0	0	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	0	302	0	435	400	527	0	174	1838
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	0	4	0	0	0	0	0	0	4
89502376	REBUILD EXISTING HANDHOLE	EACH	0	0	0	0	3	0	1	3	7
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	0	0	0	0	0	0	0	196	196
X6061311	CONCRETE MEDIAN SURFACE, 5 INCH	SQ FT	0	0	0	0	0	0	0	196	196
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	0	437	37	258	282	100	172	311	1597

HOT-MIX ASPHALT MIXTURE REQUIREMENTS	
Mixture Type	Air Voids @ Ndes
CLASS D PATCHES (HMA BINDER IL - 19 mm) 9"	4% at 70 GYR.
HMA REPLACEMENT OVER PATCHES (HMA Surface Course, Mix "D", N70) 1 1/2"	4% at 70 GYR.

NOTE:
THE ENVIRONMENTAL FIRM IS REQUIRED TO CONTINUOUSLY MONITOR FOR WORKER PROTECTION AND SOIL CONTAMINATION AT SEVERAL LOCATIONS. SEE SPECIAL PROVISION AND SUPPLEMENTAL SPECIFICATIONS FOR DETAILS.