

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0005	0042
*	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	93	93	
*	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	74	74	
	20200100	EARTH EXCAVATION	CU YD	497	497	
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1397	1397	
*	25200200	SUPPLEMENTAL WATERING	UNIT	4	4	
	28000510	INLET FILTERS	EACH	10	10	
	35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	2830	2830	
	35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	67	67	
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2514	2514	
	40600300	AGGREGATE (PRIME COAT)	TON	51	51	
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10	
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	76	76	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	299	299	
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	324	324	
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2476	2476	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	677	677	
	42400800	DETECTABLE WARNINGS	SQ FT	281	281	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	1763	1763	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	62	62	
	44000600	SIDEWALK REMOVAL	SQ FT	12999	12999	
	44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	5	5	
	44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	15	15	

* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	0005	0042
	44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	25	25	
	44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	50	50	
*	56400100	FIRE HYDRANTS TO BE MOVED	EACH	4	4	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	32	32	
	60255500	MANHOLES TO BE ADJUSTED	EACH	17	17	
	60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3	
	60260100	INLETS TO BE ADJUSTED	EACH	19	19	
	60262700	INLETS TO BE RECONSTRUCTED	EACH	2	2	
	60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	2	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	12	12	
	67100100	MOBILIZATION	L SUM	1	1	
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	20000	20000	
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6667	6667	
*	72000100	SIGN PANEL - TYPE 1	SQ FT	116	116	
*	72900200	METAL POST - TYPE B	FOOT	294	294	
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1734	1734	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	19339	19339	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2457	2457	
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1545	1545	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	216	216	

* - INDICATES SPECIALTY ITEMS

FILE NAME = 13308-QUAN-01 - IDOT P01	USER NAME =	DESIGNED - JPH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	OAK PARK AVENUE ROADWAY IMPROVEMENTS SUMMARY OF QUANTITIES & GENERAL NOTES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	CHECKED - PKB	REVISED -	2774			13-00115-00-RS	COOK	35	2	
	PLOT SCALE =	DRAWN - RG	REVISED -			CONTRACT NO. 61A01				
	PLOT DATE = 12-02-13	CHECKED - AG	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT CMM-4003 (249)				
				SCALE:	SHEET NO. 2 OF 35 SHEETS	STA.	TO STA.			