

66600105 - FURNISHING AND ERECTING ROW MARKERS

LOCATION	QUANTITY (EACH)
IL ROUTE 2	
982+10.66 217.37' LT	1
992+00.00 182.88' RT	1
993+00.00 200.00' RT	1
996+00.00 200.00' RT	1
997+00.00 205.00' RT	1
1000+00.00 190.00' RT	1
1002+05.31 144.34' RT	1
1003+00.00 145.00' RT	1
1004+00.00 145.00' RT	1
1005+00.00 128.65' RT	1
ROSCOE ROAD	
9017+00.00 40.09' LT	1
9017+00.00 30.91' RT	1
9018+00.00 50.00' RT	1
9019+00.00 60.00' LT	1
9020+00.00 50.00' RT	1
9022+49.78 60.00' LT	1
9023+20.90 60.00' LT	1
9024+00.00 55.00' RT	1
9025+50.00 60.00' LT	1
9025+50.00 55.00' RT	1
9030+00.00 80.00 RT	1
9029+96.27 75.00' LT	1
9032+00.00 75.00' LT	1
9033+00.00 75.00' RT	1
9035+00.00 65.00' RT	1
9036+00.00 55.00' LT	1
9037+00.00 50.00' RT	1
9040+00.00 50.00' LT	1
9040+00.00 50.00' RT	1
9041+00.00 40.76' LT	1
9041+00.00 39.24' RT	1
FRONTAGE ROAD	
2985+25.00 60.00' LT	1
2985+75.00 135.00' LT	1
2986+50.00 135.00' LT	1
2987+00.00 115.00' LT	1
2987+75.00 60.00' RT	1
2989+00.00 45.00' LT	1
2990+00.00 45.00' LT	1
2990+77.77 30.07' LT	1
2999+20.58 60.00' RT	1
3000+00.00 60.00' LT	1
3001+00.00 40.00' LT	1
3001+20.00 70.00' LT	1
3001+75.00 70.00' RT	1
3002+00.00 40.00' LT	1
3004+00.00 40.00' LT	1
3006+00.00 65.00' LT	1
3007+00.00 31.40' LT	1

FURNISHING AND ERECTING ROW MARKERS, TOTAL= 48

EACH

SEE PLAT OF HIGHWAYS FOR EXACT LOCATION OF ROW MARKERS.

70106800 - CHANGEABLE MESSAGE SIGNS

LOCATION	NUMBER OF SIGNS PER LOCATION	(CAL MO)	TOTAL (CAL MO)
STAGE 1			
IL ROUTE 2, SB	1	0.5	0.5
IL ROUTE 2, NB	1	0.5	0.5
ROSCOE	2	0.5	1
STAGE 2			
IL ROUTE 2, SB	1	0.5	0.5
IL ROUTE 2, NB	1	0.5	0.5
ROSCOE	2	0.5	1

CHANGEABLE MESSAGE SIGNS, TOTAL= 4
CAL MO

70300100 - SHORT TERM PAVEMENT MARKING

	TOTAL LENGTH (FOOT)	LENGTH (FOOT)*
PAVEMENT MARKING	44,972	4497

SHORT TERM PAVEMENT MARKING, TOTAL= 4,497
FOOT

LENGTH OF SHORT TERM PAVEMENT MARKING = (PERM. MARKING LENGTH/40)*4

70301000 - WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	4" DOUBLE SOLID YELLOW (SQ FT)	4" SOLID YELLOW (SQ FT)	4" WHITE SOLID (SQ FT)	8" WHITE SOLID (SQ FT)	12" WHITE SOLID (SQ FT)	12" YELLOW SOLID (SQ FT)	24" WHITE STOP BAR (SQ FT)	WORDS & ARROWS (RURAL) (SQ FT)
REMOVED AFTER STAGE 1								
999+18.00 TO 1015+00.00	118	119	527					
1015+00.00 TO 1020+47.50			153					
SUBTOTAL STAGE 1	118	119	680					
REMOVED AFTER STAGE 1A								
960+28.00 TO 965+23.82	327							
1005+89.00 TO 1015+00.00		304	717					
1015+00.00 TO 1022+60.00		253						
ROSCOE ROAD				117				156
SUBTOTAL STAGE 1A	327	557	717	117	0	0	0	156
REMOVED AFTER STAGE 2								
960+53.82 TO 973+00.00	773	57	830					
973+00.00 TO 986+90.00	233	647	747	81		114		47
986+90.00 TO 989+00.00	140		67					
1007+30.00 TO 1015+00.00		257	257					
1015+00.00 TO 1019+44.00		148	148					
ROSCOE ROAD		176	73	243	249		60	94
SUBTOTAL STAGE 2	1,147	1,284	2,121	323	249	114	60	140
REMOVED AFTER STAGE 3								
986+90.00 TO 1000+85.00	140	379	191					
1000+85.00 TO 1015+00.00		472	472					
1015+00.00 TO 1036+15.00		938	390					
SUBTOTAL STAGE 3	140	1,789	1,052	0	0	0	0	0
TOTAL	1,731	3,749	4,571	441	249	114	60	296

WORK ZONE PAVEMENT MARKING REMOVAL,
TOTAL= 11,211 SQ. FT.

TEMPORARY PAVEMENT MARKINGS PLACED PRIOR TO PLACEMENT OF HOT-MIX ASPHALT SURFACE COURSE ON IL ROUTE 2 SHALL BE PAVED OVER.

TEMPORARY PAVEMENT MARKINGS

	LOCATION	4" WHITE (FOOT)	4" YELLOW (FOOT)	4" DOUBLE YELLOW (FOOT)	4" YELLOW SKIP-DASH (FOOT)	8" WHITE (FOOT)	12" WHITE (FOOT)	12" YELLOW (FOOT)	24" STOP BAR (FOOT)	ARROWS (SF)	TEMP. RPM (EACH)
STAGE 1	960+27.59 TO 973+00.00	2,490		2,543							
	973+00.00 TO 986+90.00	894		754							
	999+18.17 TO 1000+85.00	182		364							
	1000+85.00 TO 1015+00.00	1,408	1,264	263							
	1015+00.00 TO 1022+60.00	458	760								
	SUBTOTAL STAGE 1	5,431	2,024	3,924							
STAGE 1A	1001+00.00 TO 1015+00.00		965								
	ROSCOE ROAD										
	9027+80.00 TO 9031+47.16	609	669			361			28	156	
	SUBTOTAL STAGE 1A	609	1,634			361			28	156	
STAGE 2	960+53.82 TO 973+00.00	2,490	170	2,320							
	973+00.00 TO 986+90.00	2,590	1,940	700		121		114		47	
	986+90.00 TO 1000+85.00	2,795	1,615	1,170							27
	1000+85.00 TO 1015+00.00	2,830	2,830								8
	1015+00.00 TO 1036+15.00	790	2,575								
ROSCOE ROAD											
9021+50.00 TO 9031+47.16					192	249		30	16		
SUBTOTAL STAGE 2	11,495	9,130	4,190		313	249	114	30	63	35	
STAGE 3	959+83.72 TO 973+00.00	2633	305	1,589	192			80			
	973+00.00 TO 986+90.00	3,047	1,441	2,178		1,571	507	212			
	986+90.00 TO 992+77.00			1,304				7			
	992+77.00 TO 1015+00.00	2,830	2,830								
	1015+00.00 TO 1036+15.00	1,495	2,165								
SUBTOTAL STAGE 3	10,005	6,741	5,071		1,571			0	0		
TOTAL			60,254			2,245	249	114	58	219	35

70300210 TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	219	SQ FT
70300220 TEMPORARY PAVEMENT MARKING - LINE 4"	60,254	FOOT
70300250 TEMPORARY PAVEMENT MARKING - LINE 8"	2,245	FOOT
700300260 TEMPORARY PAVEMENT MARKING - LINE - 12"	363	FOOT
70300280 TEMPORARY PAVEMENT MARKING - LINE 24"	58	FOOT
78100200 TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	35	EACH

70400100 - TEMPORARY CONCRETE BARRIER

LOCATION	LENGTH FOOT
EX. IL ROUTE 2	
970+82.57 TO 974+81.58 RT	400.0

TEMPORARY CONCRETE BARRIER, TOTAL= 400.0 FEET