



REMOVALS LEGEND

- PAVEMENT REMOVAL
- PAVED SHOULDER REMOVAL
- TREE REMOVAL ACRES
- TREE REMOVAL (UNIT DIAMETER)
- FENCE REMOVAL
- GUARDRAIL REMOVAL

EXISTING UTILITIES LEGEND

- UNDERGROUND TELEPHONE LINE
- UNDERGROUND FIBER OPTIC LINE
- UNDERGROUND GAS LINE
- AERIAL LINE

EXISTING PLAN AND REMOVAL NOTES

ADDITIONAL REMOVALS SHOWN IN THE DRAINAGE PLANS.
 ALL FENCE MATERIAL OTHER THAN CHAIN LINK WILL BE INCLUDED IN CLEARING.
 BITUMINOUS DRIVEWAYS ON AGGREGATE BASE COURSE REMOVAL WILL BE PART OF EARTH EXCAVATION.
 ANY HOT-MIX ASPHALT REMOVAL WHICH IS LESS THAN 6" IN THICKNESS WILL BE INCLUDED IN EARTH EXCAVATION.
 MAILBOX LOCATIONS WILL BE UPDATED BASED ON DISTRICT 2 STANDARDS (SEE GENERAL NOTES).
 FOR ROW, TEMPORARY AND PERMANENT EASEMENTS INFORMATION SEE PLAT OF HIGHWAYS.

***0.04 ACRE TREE REMOVAL**

STATION	OFFSET
999+17.32	279.25' LT
999+17.32	256.37' LT
999+40.20	279.63' LT
999+55.42	279.63' LT
999+63.24	272.57' LT
1000+01.67	256.65' LT
1000+12.17	266.91' LT
1000+14.27	261.42' LT
1000+15.43	264.23' LT

***0.003 ACRE TREE REMOVAL**

STATION	OFFSET
1006+08.37	79.78' RT
1006+11.83	74.78' RT
1006+25.24	73.33' RT
1006+52.60	73.13' RT

***0.02 ACRE TREE REMOVAL**

STATION	OFFSET
1006+39.05	23.71' RT
1006+47.73	29.94' RT
1006+52.62	19.87' RT
1006+62.16	21.85' RT
1006+73.87	39.27' RT
1006+99.45	42.29' RT
1007+00	22.24' RT

***0.002 ACRE TREE REMOVAL**

STATION	OFFSET
1000+53.48	265.24' LT
1000+59.82	258.09' LT
1000+68.95	256.04' LT
1000+80.59	255.75' LT
1000+95.03	255.73' LT

***0.12 ACRE TREE REMOVAL**

STATION	OFFSET
1000+95.03	255.74' LT
1001+19.59	292.70' LT
1001+38.74	252.93' LT
1001+55.59	292.89' LT
1001+75.47	252.58' LT
1001+92.32	259.71' LT
1002+21.36	251.22' LT
1002+52.29	250.62' LT
1002+72.02	248.93' LT
1002+74.15	259.75' LT
1002+99.33	245.80' LT
1003+28.50	243.94' LT
1003+38.64	247.22' LT
1003+80.83	259.04' LT

***6.41 ACRE TREE REMOVAL REMOVAL SHEET 3**

STATION	OFFSET
992+99.05	196.60' LT
993+00	0.00' LT
993+00	121.00' LT
994+00	110.04' RT
995+00	140.86' RT
996+00	121.94' RT
996+05.13	204.69' LT
997+00	136.09' RT
997+76.97	196.08' LT
999+00	139.44' RT
999+26.97	162.09' LT
1000+50	131.91' RT
1001+29.57	175.22' LT
1002+00	125.43' RT
1002+22.57	119.94' LT
1002+22.70	25.45' RT
1003+04.78	25.09' RT
1003+07.66	99.50' RT

FILE NAME =	USER NAME =	DESIGNED - RDT	REVISED -
ei:\pw\work\p\dtdot\undbladerr\d0331855\0264h70-sht-rem-03.dgn		DRAWN - RDT	REVISED -
PLOT SCALE =	CHECKED - GC	REVISOR -	REVISED -
PLOT DATE	DATE - 10/05/2012	REVISOR -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 2
EXISTING PLAN AND REMOVALS 3**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	77R-1	WINNEBAGO	179	28
CONTRACT NO. 64H70				

SCALE: 1"=50' SHEET NO. 28 OF 179 SHEETS STA. 993+00 TO STA. 1007+00

ILLINOIS FED. AID PROJECT