

PAVEMENT MARKING SCHEDULE

LOCATION	LENGTH	THERMO PAVT MKG 4"		THERMO PAVT MKG 6"		THERMO PAVT MKG 8"	THERMO PAVT MKG 12"		THERMO PAVT MKG 24"	PREFORM PLASTIC PAVT MKG 4"		PREFORM PLASTIC PAVT MKG LET & SYM	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVT MARK REM	
		YEL	WHT	YEL	WHT	WHT	YEL	WHT	WHT	YEL	WHT	SO FT	FOOT	SO. FT.	
STA		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	
0+00 TO 4+57	457												365.6	30	
4" WHITE EDGELINES			914												
4" YELLOW CENTERLINE		1828													
4+57 TO 17+35	1278												1022.4	85	
4" WHITE EDGELINES			2556												
4" YELLOW CENTERLINE		2556													
8" WHITE LEFT TURN BAY						354									
8" WHITE LEFT TURN BAY SKIP DASH						42									
8" WHITE PAINTED ISLAND, RAMP D						50									
12" YELLOW DIAGONAL CENTERLINE							80								
24" WHITE STOP BARS RAMP D									45						
LEFT TURN ARROWS LARGE												46.8	576.0	48	
17+35 TO 19+54	219												175.2	15	
4" WHITE EDGELINES															
4" YELLOW CENTERLINE										438	438				
19+54 TO 31+41	1187												949.6	79	
4" WHITE EDGELINES			2374												
4" YELLOW CENTERLINE		2374													
8" WHITE LEFT TURN BAY						325									
8" WHITE LEFT TURN BAY SKIP DASH						40									
8" WHITE RIGHT TURN BAY						304									
8" WHITE RIGHT TURN BAY SKIP DASH						42									
8" WHITE PAINTED ISLAND, RAMP A						220									
8" WHITE PAINTED ISLAND, RAMP B						50									
24" WHITE STOP BARS, RAMP B									45						
LEFT TURN ARROWS LARGE												93.6	1152.0	96	
31+41 TO 40+93	952												380.8	32	
4" YELLOW BI-DIRECTIONAL TURN LANE		1702											150.0	12	
6" YELLOW BI-DIRECTIONAL TURN LANE					324										
12" YELLOW DIAGONALS							90								
24" WHITE STOP BARS SIDESTREETS															
LEFT TURN ARROWS LARGE												124.8	1536.0	128	
40+93 TO 65+00	2407												962.8	80	
6" YELLOW CENTERLINE															
4" WHITE SKIP DASH AT CASEY'S		50			602										
24" WHITE STOP BARS PATTON AND MARKET															
6" WHITE CROSSWALKS PATTON AND MARKET									95						
65+00 TO 67+76	276												110.4	9	
4" YELLOW CENTERLINE		96													
4" YELLOW CENTERLINE ACROSS BRIDGE										456					
67+76 TO 115+80	4804														
PVT MK FOR LEFT TURN LANE BAY PATTON AND RAILROAD RD, S LEG		1278				141	88		60				350.0	29	
PVT MK FOR LEFT TURN LANE BAY PATTON AND RAILROAD RD, N LEG		1278				141	88		54				350.0	29	
6" WHITE CROSSWALKS PATTON AND RAILROAD RD					400										
8" WHITE ISLANDS PATTON AND RAILROAD RD						173									
12" WHITE DIAGONALS, ISLANDS PATTON AND RR RD								35							
LEFT TURN ARROWS LARGE PATTON AND RR RD												62.4	768.0	64	
6" WHITE CROSSWALKS ORLEANS ST AND RAILROAD RD(PED. XWALK)						80									
6" WHITE CROSSWALKS E CENTER ST AND RAILROAD RD						160									
PVT MK FOR LEFT TURN LANE BAY PELL'S AND RAILROAD RD, S LEG		1142				121	80		37				350.0	29	
PVT MK FOR LEFT TURN LANE BAY PELL'S AND RAILROAD RD, N LEG		1120				130	78		27				350.0	29	
PVT MK FOR LEFT TURN LANE BAY PELL'S AND RAILROAD RD, E LEG		1236				130	90		38				350.0	29	
6" WHITE CROSSWALKS PATTON AND RAILROAD RD															
LEFT TURN ARROWS LARGE PELL'S AND RR RD												78.0	960.0	80	
6" YELLOW CENTERLINE PATTON TO PELL'S					101										
6" YELLOW CENTERLINE PELL'S TO FALL ST					794										
4" WHITE EDGELINES FOR PARKING LANE(VERMILLION ST TO FALL ST)					5970										
6" WHITE CROSSWALKS VERMILLION ST AND IL 9								280							
115+80 TO 123+30	1350												540.0	45	
6" YELLOW CENTERLINE															
4" WHITE EDGELINES					2700.0										
GRAND TOTAL		12930	14660	14514	2159	1245	2263	594	35	401	894	438	406	11399	949

PREFORMED PLASTIC PAVEMENT MARKINGS TO BE USED ON BRIDGES ONLY.
CROSSWALKS ON VERMILLION ROAD SHALL HAVE LADDERS ON THEM. PLACE THEM ON ALL FOUR LEGS OF INTERSECTIION

FILE NAME =	USER NAME = *USER*	DESIGNED - ___	REVISED - ___	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL		DRAWN - ___	REVISED - ___			697	(17) RS-4	FORD	31	12	
Default		CHECKED - ___	REVISED - ___			CONTRACT NO. 66A94					
		DATE - ___	REVISED - ___			SCALE: _____	SHEET _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		