



TEMPORARY INFORMATION SIGNING

NOTES:

1. USE 6" D BLACK LETTERING ON FLOURESENT ORANGE BACKGROUND.
2. ERECT SIGNS AT LOCATIONS IN ADVANCE OF THE "ROAD CONSTRUCTION AHEAD" SIGNS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② A MINIMUM OF ONE WEEK PRIOR TO THE START OF THE LANE CLOSURE.
4. REMOVE PANEL ② ON THAT DATE.
5. SEE SPECIAL PROVISION "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. WILL BE PAID FOR PER SO FT AS "TEMPORARY INFORMATION SIGNING". EACH SIGN = 21 SO FT AND THE DATE PANEL ② WILL NOT BE MEASURED SEPARATELY FOR PAYMENT.
7. TOTAL QUANTITY OF 4 SIGNS NEEDED.
1 EA. AT BEGINNING OF JOB AND END OF JOB
ALSO 1 EA. ON EACH LEG OF
RT 45 APPROACHING RT 9.

FILE NAME =	USER NAME = \$USER*	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	DETAILS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
\$FILEL\$	PLOT SCALE = \$SCALE*	DRAWN - _____	REVISED - _____			697	(17) RS-4	FORD	31	24	
\$MODELNAME\$	PLOT DATE = \$DATE*	CHECKED - _____	REVISED - _____			CONTRACT NO. 66A94					
		DATE - _____	REVISED - _____			ILLINOIS FED. AID PROJECT					