

CODE NO.	ITEM	UNIT	CONSTR. CODE
			CONTRACT MAINT
			100% STATE
			ROADWAY
			0014
			RURAL
50102400	CONCRETE REMOVAL	CU YD	179.2
50300100	FLOOR DRAINS	EACH	14
50300255	CONCRETE SUPERSTRUCTURE	CU YD	197
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	60740
50300300	PROTECTIVE COAT	SQ YD	500
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1214
50800515	BAR SPLICERS	EACH	72
50800530	MECHANICAL SPLICERS	EACH	1416
52000110	PREFORMED JOINT STRIP SEAL	FOOT	169
67100100	MOBILIZATION	L SUM	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	395
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1105
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3
* 78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	2214
* 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	1150
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1306
X0326867	RADAR SPEED TRAILER	CAL MO	3
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	350
X0326907	PORTABLE, VEHICLE MOUNTED, CHANGEABLE MESSAGE SIGN	CAL MO	2
X7010208	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1

\* SPECIALITY ITEMS

FILE NAME =	USER NAME = Pateljy	DESIGNED - RW	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p-work\p-dot\pateljy\0325905\0366	01-shr-detaila.dgn	DRAWN - RW	REVISED -			57	38-6B11-2	IRROODIS	19	3	
	PLOT SCALE = 100.0000 1/4 in.	CHECKED -	REVISED -			CONTRACT NO. 66CBI					
MODELNAME#	PLOT DATE = 1/15/2014	DATE -	REVISED -			SCALE:	SHEET 1 OF 1 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	