

I-55 MAINLINE SHOULDER TABLE

			EXC & GR EXISTING SHOULDER	HMA BINDER CSE. IL 19.0 FG N50	HMA SURF. CSE. IL 9.5 FG N50	HMA SURF. REM. 3"	HMA SURF. REM. 10"	SHLDR RUMBLE STRIPS 16"	BIT PRIME COAT	
I-55 NORTHBOUND			LENGTH	UNIT	TON	TON	SQ YD	SQ YD	FOOT	LBS
STA EQ. 655+49.51 BK = 150+05.99 AH										
START PROJECT	INSIDE SHLDR	STA 655+49.51 TO STA 265+00.00	11494.01	114.94		1287.3	7662.7		11494.01	3448.2
	INSIDE SHLDR	STA 265+00.00 TO STA 275+50.00	1050						1050	
	INSIDE SHLDR	STA 275+50.00 TO STA 437+42.00	16192	161.92		1813.5	10794.7		16192	4857.6
	INSIDE SHLDR	STA 437+42.00 TO STA 441+00.00	358						358	
	INSIDE SHLDR	STA 441+00.00 TO STA 460+00.00	1900	19		212.8	1266.7		1900	570
	OUTSIDE SHLDR	STA 655+49.51 TO STA 226+35.00	7629.01	76.29	996.9	1424.1	5933.7	2543	7629.01	9536.3
	OUTSIDE SHLDR	STA 229+38.00 TO STA 260+54.00	3116	31.16	407.2	581.7	2423.6	1038.7	3116	3895
	OUTSIDE SHLDR	STA 268+04.00 TO STA 283+00.00	1496						1496	
	OUTSIDE SHLDR	STA 283+00.00 TO STA 376+58.00	9358	93.58	1222.8	1746.8	7278.4	3119.3	9358	11697.5
	OUTSIDE SHLDR	STA 381+88.00 TO STA 411+82.00	2994	29.94	391.2	558.9	2328.7	998	2994	3742.5
	OUTSIDE SHLDR	STA 419+32.00 TO STA 437+42.00	1810	18.1	236.5	337.9	1407.8	603.3	1810	2262.5
	OUTSIDE SHLDR	STA 437+42.00 TO STA 441+00.00	358						358	
	OUTSIDE SHLDR	STA 441+00.00 TO STA 460+00.00	1900	19	248.3	354.7	1477.8	633.3	1900	2375
NORTHBOUND TOTAL			59655.02	563.93	3502.9	8317.7	40574.1	8935.6	59655.02	42384.6
I-55 SOUTHBOUND										
START PROJECT	INSIDE SHLDR	STA 655+49.51 TO STA 265+00.00	11494.01	114.94		1287.3	7662.7		11494.01	3448.2
	INSIDE SHLDR	STA 265+00.00 TO STA 275+50.00	1050						1050	
	INSIDE SHLDR	STA 275+50.00 TO STA 437+98.00	16248	162.48		1819.8	10832		16248	4874.4
	INSIDE SHLDR	STA 437+98.00 TO STA 440+96.00	298						298	
	INSIDE SHLDR	STA 440+96.00 TO STA 460+00.00	1904	19.04		213.2	1269.3		1904	571.2
	OUTSIDE SHLDR	STA 655+49.51 TO STA 220+24.00	7018.01	70.18	917	1310	5458.5	2339.3	7018.01	8772.5
	OUTSIDE SHLDR	STA 227+74.00 TO STA 260+62.00	3288	32.88	429.6	613.8	2557.3	1096	3288	4110
	OUTSIDE SHLDR	STA 263+66.00 TO STA 265+00.00	134	1.34	17.5	25	104.2	44.7	134	167.5
	OUTSIDE SHLDR	STA 265+00.00 TO STA 283+00.00	1800						1800	
	OUTSIDE SHLDR	STA 283+00.00 TO STA 373+22.00	9022	90.22	1178.9	1684.1	7017.1	3007.3	9022	11277.5
	OUTSIDE SHLDR	STA 380+72.00 TO STA 414+71.00	3399	33.99	444.1	634.5	2643.7	1133	3399	4248.8
	OUTSIDE SHLDR	STA 417+74.00 TO STA 437+98.00	2024	20.24	264.5	377.8	1574.2	674.7	2024	2530
	OUTSIDE SHLDR	STA 437+98.00 TO STA 440+96.00	298						298	
	OUTSIDE SHLDR	STA 440+96.00 TO STA 460+00.00	1904	19.04	248.8	355.4	1480.9	634.7	1904	2380
SOUTHBOUND TOTAL			59881.02	564.35	3500.4	8320.9	40599.9	8929.7	59881.02	42380.1
GRAND TOTAL			119536.04	1128.28	7003.3	16638.6	81174	17865.3	119536.04	84764.7

I-55 RAMP SHOULDER TABLE

			EXC & GR EXISTING SHOULDER	HMA BINDER CSE. IL 19.0 FG N50	HMA SURF. CSE. IL 9.5 FG N50	HMA SURF. REM. 3"	HMA SURF. REM. 10"	SHLDR RUMBLE STRIPS 16"	BIT PRIME COAT
LOCATION	STATION	LENGTH	UNIT	TON	TON	SQ YD	SQ YD	FOOT	LBS
IL 17 NE OUTSIDE	STA 24+47.00 TO STA 35+00.00	1053						1053	
TOTAL		1053	0	0	0	0	0	1053	0