

LOCATION: FAP 721 (IL 10)

PIATT COUNTY

RURAL

FUNDING BREAKOUT: 80% FEDERAL

20% STATE

CONSTRUCTION CODE: 0014

PAY ITEM CODE	PAY ITEM DESCRIPTION	UNIT	QTY.
50102400	CONCRETE REMOVAL	CU YD	2.6
50300225	CONCRETE STRUCTURES	CU YD	21.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	99.2
50300260	BRIDGE DECK GROOVING	SQ YD	375.0
50300300	PROTECTIVE COAT	SQ YD	375.0
50400305	PRECAST PRESTRESSED CONCRETE DECK BEAMS (17" DEPTH)	SQ FT	1,393.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	26,880.0
50800515	BAR SPLICERS	EACH	265.0
50901050	STEEL RAILING, TYPE SM	FOOT	85.0
51500100	NAME PLATES	EACH	1.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	33.0
59000200	EPOXY CRACK INJECTION	FOOT	8.0
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	450.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4.0

*

*

14

* SPECIALTY ITEMS

CB Coombe-Bloxdorf P.C.
 - CIVIL ENGINEERS -
 - STRUCTURAL ENGINEERS -
 - LAND SURVEYORS -
 Design Firm License No. 184-002703

FILE NAME :	USER NAME : gmezianoje	DESIGNED - MCB	REVISED -
\\pvc\work\p\dot\gmezianoje\101345901\70432-sh1-003-summary-quantities-001.dgn		DRAWN - CFC	REVISED -
		CHECKED - MCB	REVISED -
		DATE - / /	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 2 OF 4 SHEETS
STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
721	(115BR) BR	PIATT	39	4
CONTRACT NO. 70432			ILLINOIS FED. AID PROJECT	