

FAS 1512 (US-150)
 VERMILION CO.
 RURAL
 TWO-LANE
 100% STATE
 S. N. 092-0050
 CONSTRUCTION TYPE CODE: 0014

CODE NO	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	11.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	110.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	107.0
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	30.0
50102400	CONCRETE REMOVAL	CU YD	9.1
50300100	FLOOR DRAINS	EACH	22.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.2
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1690.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1230.0
50800515	BAR SPLICERS	EACH	22.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	66.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	5.0
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	5.0
52100520	ANCHOR BOLTS, 1"	EACH	20.0

2.0/16/12

FILE NAME =	USER NAME = gearlock_jd	DESIGNED - GMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\gearlock_jd\0208772\070965-sht-500.dgn	DRAWN - GMS	REVISED -	1512			36 BDR	VERMILION	34	3	
PLOT SCALE = 42,000' / in.	CHECKED -	REVISED -	CONTRACT NO. 70965							
PLOT DATE = 2/25/2013	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							