

FAS 1512 (US-150)  
 VERMILION CO.  
 RURAL  
 TWO-LANE  
 100% STATE  
 S. N. 092-0050  
 CONSTRUCTION TYPE CODE: 0014

CODE NO	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	1205.0
67100100	MOBILIZATION	L SUM	1.0
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0
70106700	TEMPORARY RUMBLE STRIPS	EACH	6.0
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2.0
70800105	TEMPORARY WATER FILLED BARRIER	FOOT	662.5
78001110	PAINT PAVEMENT MARKING - LINE4"	FOOT	1317.0
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6.0
X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SO YD	22.0

\* SPECIALTY ITEM

FILE NAME *	USER NAME * cmarlockjd	DESIGNED - GMS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
01\pwork\pvidot\cmarlock_jd\028077210	078905-sh1-500.dgn	DRAWN - GMS	REVISED -			1512	36 BDR	VERMILION	34	4	
PLOT SCALE * 48.0001' / 1"	CHECKED -	REVISED -	REVISED -			CONTRACT NO. 70965					
PLOT DATE * 10/3/2013	DATE -	REVISED -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					