
HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

	STATION	<u>TO</u> <u>S</u>	TATION
RAMP I-CA:	A 222+07.00	22	22+12.00 B
RAMP I-BD:	B 52+55.00	5	52+60.00 A
RAMP I-BC:	(A) 166+70.00	16	6+75.00 B
RAMP I-BC:	B 180+45.00	18	30+50.00 (A)
RAMP I-DB:	A 126+70.00	1 2	26+75.00 B
RAMP I-DB:	B 141+85.00	1 4	11+90.00 A
RAMP I-AC:	B 12+31.00	1	2+36.00 (A)
RAMP I-AD:	A 87+00.00	8	37+05.00 B
RAMP I-AD:	B 100+51.00	1 C	00+56.00 (A)
RAMP I-CB:	A 62+00.00	6	52+05.00 B
RAMP I-CB:	(B) 71+77.00	7	1+82.00 (A)

TYPICAL PROFILE



GENERAL NOTES

THE WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE ARTICLES OF SECTION 406 OF THE STANDARD SPECIFICATIONS.


THE WORK SHALL BE COMPLETED UNDER RAMP CLOSURE FOR THE HIGH FRICTION SURFACE TREATMENT OPERATIONS.

THE INTENT IS TO INLAY THE HIGH FRICTION SURFACE TREATMENT AT THE BEGINNING AND END OF THE RAMPS TO ALLOW THE MATERIAL TO BE FLUSH WITH THE EXISTING PAVEMENT. ADJUSTMENTS TO THE DEPTH OF THE BUTT JOINT MAY BE REQUIRED TO MEET FIELD CONDITIONS AND WILL BE DETERMINED BY THE ENGINEER.

PORTLAND CEMENT CONCRETE SURFACE REMOVAL — BUTT JOINT

	STATION	<u>TO</u>	STATION	
RAMP I-CA:	© 206+70.00		206+75.00 D	
RAMP I-BD:	© 42+06.00		42+11.00 D	
RAMP I-DA:	© 22+00.00		22+05.00 D	
RAMP I-DA:	D 31+65.00		31+70.00 ©	
RAMP I-AC:	(C) 2+20.00		2+25.00 D	

TYPICAL PROFILE



GENERAL NOTES

THE WORK SHALL BE PERFORMED IN ACCORDANCE WITH APPLICABLE ARTICLES OF SECTION 406 OF THE STANDARD SPECIFICATIONS.

THE WORK SHALL BE COMPLETED UNDER RAMP CLOSURE FOR THE HIGH FRICTION SURFACE TREATMENT OPERATIONS.

THE INTENT IS TO INLAY THE HIGH FRICTION SURFACE TREATMENT AT THE BEGINNING AND END OF THE RAMPS TO ALLOW THE MATERIAL TO BE FLUSH WITH THE EXISTING PAVEMENT. ADJUSTMENTS TO THE DEPTH OF THE BUTT JOINT MAY BE REQUIRED TO MEET FIELD CONDITIONS AND WILL BE DETERMINED BY THE ENGINEER.

FILE NAME =	USER NAME = eaglinga	DESIGNED - GAE	REVISED -
c:\pw_work\pwidot\eaglinga\d0363405\D57	A52-sht-details.dgn	DRAWN - GAE	REVISED -
	PLOT SCALE = 40.0000 '/ in.	CHECKED -	REVISED -
\$MODELNAME\$	PLOT DATE = 12/6/2013	DATE -	REVISED -

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

SCALE:

DETAIL FOR HMA & PCC SURFACE REMOVAL — BUTT JOINT			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.			
			57	HFSC 2014-1	CHAMPAIGN	31	27			
					CONTRACT	NO. 7	70A52			
	SHEET 1	OF 1	SHEETS	STA.	TO STA.		ILLINOIS FED. A	ID PROJECT		