

PATCHING SCHEDULE

LANE	CLASS D PATCHES, TYPE			
	CLASS I, 14 INCH	CLASS II, 14 INCH	CLASS III, 14 INCH	CLASS IV, 14 INCH
	SQ YD	SQ YD	SQ YD	SQ YD
NORTHBOUND	20	893	69.0	60.0
SOUTHBOUND	20	800	0.0	93.0
TOTALS:	40	1693	69	153

STRIPING SCHEDULE

STATION TO STATION			PAINT PAVEMENT MARKING - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	
			FOOT	FOOT	FOOT	SQ FT	EACH	
213+50	TO	380+00	36428	50	3330	555	208	
380+00	TO	388+74	BRIDGE OMISSION					
388+74	TO	408+44	4179	-	394	66	25	
408+44	TO	411+30	BRIDGE OMISSION					
411+30	TO	497+03	18781	-	1715	286	147	
497+02.80	TO	499+22.70	BRIDGE OMISSION					
499+23	TO	507+00	1749	-	155	26	10	
507+00	TO	508+16	BRIDGE OMISSION					
508+16	TO	547+41	8831	-	785	131	49	
547+41.00	TO	547+29.00	BRIDGE OMISSION					
547+29	TO	595+66	10409	-	967	161	73	
595+66.10	TO	595+91.80	BRIDGE OMISSION					
595+92	TO	608+20	2708	-	246	41	46	
608+20.10	TO	608+33.90	BRIDGE OMISSION					
608+34	TO	719+10	24609	-	2215	369	138	
719+10	TO	719+94	BRIDGE OMISSION					
719+94	TO	762+13	8943	-	844	141	93	
762+13.20	TO	762+05.10	BRIDGE OMISSION					
762+05	TO	884+90	27328	-	2457	409	154	
884+90	TO	892+30	BRIDGE OMISSION					
892+30	TO	915+44	5207	-	463	77	29	
NO PASSING ZONES								
SOUTHBOUND:								
323+53	TO	328+65	512	-	-	-	-	
350+80	TO	372+98	2218	-	-	-	-	
397+52	TO	415+13	1761	-	-	-	-	
424+24	TO	431+90	766	-	-	-	-	
715+80	TO	748+05	3225	-	-	-	-	
755+60	TO	762+24	664	-	-	-	-	
780+90	TO	786+50	560	-	-	-	-	
806+30	TO	813+44	714	-	-	-	-	
834+40	TO	840+00	560	-	-	-	-	
860+45	TO	866+13	568	-	-	-	-	
903+07	TO	910+65	758	-	-	-	-	
NORTHBOUND:								
312+86	TO	319+01	615	-	-	-	-	
340+90	TO	362+96	2206	-	-	-	-	
388+24	TO	404+22	1598	-	-	-	-	
412+00	TO	421+00	900	-	-	-	-	
705+54	TO	737+42	3188	-	-	-	-	
748+67	TO	756+10	743	-	-	-	-	
770+00	TO	777+20	720	-	-	-	-	
796+54	TO	804+50	796	-	-	-	-	
824+43	TO	829+40	497	-	-	-	-	
851+28	TO	855+77	449	-	-	-	-	
893+42	TO	900+25	683	-	-	-	-	
TOTALS:			173871	50	13571	2262	971	

PAVEMENT SCHEDULE

STATION TO STATION			LENGTH	WIDTH	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	HMA SURFACE COURSE, MIX "C" NTO	AGGREGATE SHOULDERS, TYPE B	ADDITIONAL COMMENTS
US 51			FEET	FEET	GAL	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	
213+50	TO	228+62	1512	26	437	8.7	14	58	4368	-	367	62	
228+62	TO	231+18	256	26	131	2.6	-	-	1308	-	110	9	10' WIDE LT & RT HMA SHOULDER
231+18	TO	232+50	132	26	53	1.1	-	-	528	-	44	6	10' WIDE RT HMA SHOULDER
232+50	TO	350+00	11750	26	3394	67.9	-	-	33944	-	2851	521	
350+00	TO	369+10	1910	26	552	11.0	-	-	-	5518	463	-	
369+10	TO	380+00	1090	26	315	6.3	14	58	3149	-	265	49	
380+00	TO	388+74	874	26	BRIDGE OMISSION								
388+74	TO	403+44	1470	26	425	8.5	14	58	4247	-	357	67	
403+44	TO	408+44	500	26	144	2.9	14	-	-	1444	121	-	
408+44	TO	411+30	286	26	BRIDGE OMISSION								
411+30	TO	414+22	292	26	84	1.7	14	-	-	844	71	-	
414+22	TO	497+03	8280.8	26	2392	47.8	-	-	23922	-	2009	370	
497+02.8	TO	499+22.7	STATION EQUATION										
499+23	TO	505+05	582.3	26	168	3.4	-	-	1682	-	141	28	
505+05	TO	507+00	195	26	56	1.1	14	-	-	563	47	-	
507+00	TO	508+16	116	26	BRIDGE OMISSION								
508+16	TO	509+91	175	26	51	1.0	14	-	-	506	42	-	
509+91	TO	547+41	3750	26	1083	21.7	-	-	10833	-	910	173	
547+41.0	TO	547+29.0	STATION EQUATION										
547+29	TO	573+40	2611	26	754	15.1	-	-	7543	-	634	117	
573+40	TO	586+61	1321	26	382	7.6	-	-	-	3816	321	-	
586+61	TO	587+50	89	26	26	0.5	-	-	-	257	22	-	
587+50	TO	595+66	816.1	26	372	7.4	-	-	-	3718	312	-	15' WIDE LT HMA SHOULDER
595+66.1	TO	595+91.8	STATION EQUATION										
595+92	TO	596+50	58.2	26	17	0.3	-	-	-	168	14	-	
596+50	TO	608+20	1170.1	26	338	6.8	-	-	3380	-	284	43	
608+20.1	TO	608+33.9	STATION EQUATION										
608+34	TO	717+50	10916.1	26	3154	63.1	-	-	31535	-	2649	479	
717+50	TO	719+10	160	26	46	0.9	14	-	-	462	39	-	
719+10	TO	719+94	84	26	BRIDGE OMISSION								
719+94	TO	722+96	302	26	87	1.7	14	-	-	872	73	-	
722+96	TO	762+13	3917.2	26	1132	22.6	-	-	11316	-	951	175	
762+13.2	TO	762+05.1	STATION EQUATION										
762+05	TO	884+90	12284.9	26	3549	71.0	14	-	35490	-	2981	553	
884+90	TO	892+30	740	26	BRIDGE OMISSION								
892+30	TO	915+44	2314	26	668	13.4	29	58	6685	-	562	105	
TOTALS:					19810	396	173	231	179932	18169	16640	2758	