



TYPICAL SECTION AT MAILBOX TURNOUT

NOTE: SEE STANDARD 406201 FOR MAILBOX TURNOUT DETAILS

NOTES

THE COST OF THE ASPHALT MATERIALS, AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROADS AND APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

THE COST OF EXCAVATION IS INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

IF THERE IS NOT EXISTING HOT-MIX ASPHALT SHOULDER THEN THE ENTRANCE TAPER STARTS AT THE EDGE OF EXISTING PAVEMENT.

THE COST OF THE BITUMINOUS MATERIALS AND AGGREGATE (PRIME COAT) FOR ENTRANCES AND PUBLIC ROAD APPROACHES SHALL BE INCLUDED IN THE PAY ITEM INCIDENTAL HOT-MIX ASPHALT SURFACING.

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B
			TON	TON
RT	604+60	PE		1.9
LT	605+25	PRA	2.4	
RT	605+90	PE		1.3
RT	606+50	PE		1.4
RT	607+10	PE	1.6	
LT	607+20	CE		0.9
LT	607+83	CE		1.7
RT	607+90	PE		1.7
RT	608+44	PE		1.0
RT	609+07	PRA	0.9	
RT	609+35	PE		1.0
LT	609+45	CE	3.3	
RT	610+60	PE		1.2
RT	611+18	PE		1.3
RT	612+00	PE		1.0
RT	612+46	PE		1.1
RT	613+50	PE		1.2
RT	614+30	PE		1.1
RT	615+95	PE		0.9
LT	615+10	PE	1.2	
RT	615+28	PE		1.4

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B
			TON	TON
RT	618+45	CE		1.2
RT	620+37	PE	1.1	
RT	621+98	PE	1.0	
LT	622+54	PE		0.9
RT	622+82	PE		1.1
RT	623+65	PE		0.9
RT	624+50	PE		1.4
RT	625+78	PE		1.2
RT	626+76	PE		1.1
RT	627+23	PE		1.1
RT	629+18	PE		1.2
LT	629+20	FE		1.2
RT	629+25	PE		1.0
RT	630+93	PE		1.4
RT	631+76	PE	1.1	
RT	632+50	CE	3.2	
RT	633+29	CE	2.6	
RT	634+78	PE		1.0
LT	641+78	FE		1.6
RT	642+82	FE		0.9
RT	648+86	PRA		2.9

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B
			TON	TON
LT	649+35	PE		1.9
LT	663+25	PE		1.5
LT	669+10	CE	1.4	
LT	673+10	PE		1.4
LT	675+66	PRA	1.5	
RT	675+66	PRA		1.5
RT	688+92	FE		0.7
RT	696+75	FE		0.6
LT	702+02	PRA	1.3	
RT	702+04	PRA	1.3	
RT	704+01	FE		0.9
RT	704+52	PE		1.0
RT	705+30	PE		0.9
LT	713+15	PE		1.4
LT	714+15	PE		1.4
RT	714+15	PE		1.9
LT	725+70	FE		0.9
RT	725+47	PE		1.5
RT	726+28	PE		1.0
RT	727+90	PE		1.6
LT	728+85	CE		1.9

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B
			TON	TON
RT	739+85	FE		1.1
LT	751+17	FE		1.7
LT	751+60	FE		2.0
RT	751+75	FE		1.0
RT	752+87	PE		1.2
RT	755+94	PRA	2.4	
LT	755+97	PRA	1.8	
LT	769+15	FE		1.4
RT	775+44	FE		1.7
LT	775+60	FE		1.0
LT	788+88	FE		0.8
RT	788+88	FE		0.8
LT	789+92	PE		1.9
LT	804+12	FE		0.6
LT	807+38	PE		0.9
RT	807+38	FE		0.9
LT	809+17	PRA	2.3	
RT	809+17	PRA	2.3	
LT	809+82	CE	1.4	
RT	809+82	CE	1.4	
LT	810+86	CE	1.9	

SIDE	STATION	TYPE	INCIDENTAL HOT-MIX ASPHALT SURFACING	AGGREGATE SURFACE COURSE, TYPE B
			TON	TON
RT	811+16	CE	1.4	
RT	814+07	PE		1.9
RT	816+04	PE		0.9
RT	820+05	PE		1.1
RT	821+73	PE		1.4
LT	822+33	FE		0.8
RT	831+37	FE		1.0
LT	834+52	FE		0.7
LT	835+72	PRA	2.4	
RT	835+72	PRA		1.7
RT	837+44	FE		1.2
LT	842+10	FE		0.7
RT	848+25	FE		1.2
RT	849+47	FE		1.1
LT	860+20	PE		2.2
RT	860+45	PE		1.7
LT	861+10	PE		1.7
LT	862+28	PRA	1.8	
RT	862+28	PRA	1.8	
LT	863+37	PE		1.1
RT	863+57	FE		1.5

FE=FIELD ENTRANCE PRA - PUBLIC ROAD APPROACH
 PE=PRIVATE ENTRANCE MBT - MAILBOX TURNOUT
 CE=COMMERCIAL ENTRANCE

FILE NAME =	USER NAME = steffenmk	DESIGNED -	REVISED -
ct:\pw\work\p\dot\steffenmk\d0249366\074512-sh1-details.dgn		DRAWN -	REVISED -
PLOT SCALE = 100.0000' / 1"		CHECKED -	REVISED -
PLOT DATE = 12/5/2013		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**RURAL ENTRANCE SCHEDULE AND MAILBOX TURNOUT DETAILS
WITH SHOULDERS**

SCALE: NA SHEET NO. 2 OF 3 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	(8,9,10)RS-2	Wayne	23	10
CONTRACT NO.			74512	
ILLINOIS FED. AID PROJECT				