

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0044 EFFINGHAM COUNTY	0044 FAYETTE COUNTY
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	388	194	194
20800150	TRENCH BACKFILL	CU YD	466	457.7	8.3
28000500	INLET AND PIPE PROTECTION	EACH	14	9	5
28100105	STONE RIPRAP, CLASS A3	SO YD	39	25.5	13.5
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	388	194	194
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SO YD	264	264	
35600728	HOT-MIX ASPHALT BASE COURSE WIDENING, 13"	SO YD	502	251	251
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SO YD	931	466	465
44000100	PAVEMENT REMOVAL	SO YD	962	481	481
44000400	GUTTER REMOVAL	FOOT	2204	1102	1102
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SO YD	30	15	15
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	125	125	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		0044 EFFINGHAM COUNTY	0044 FAYETTE COUNTY
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	130	68	62
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	207	207	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	745	745	
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	4		4
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	6	5	1
60500060	REMOVING INLETS	EACH	2	1	1
60602500	CONCRETE GUTTER, TYPE A	FOOT	2204	1102	1102
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	312.5	162.5	150
* 63100041	TRAFFIC BARRIER TERMINAL, TYPE 1B	EACH	2	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	1	1

* SPECIALTY ITEM

FILE NAME =	USER NAME = toee10ygh	DESIGNED -	REVISED -
c:\pwwork\work\dot\toee10ygh\03340320\107	4627-ehs-soq.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
Default	PLOT DATE = 1/16/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2901	DT DRAINAGE REHAB 2014-1		22	3
*EFFINGHAM, FAYETTE			CONTRACT NO. 74627	
ILLINOIS FED. AID PROJECT				