

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		RURAL 90% FED 10% STATE 0005	---	---
20200100	EARTH EXCAVATION	CU YD	4673	4673		
25000210	SEEDING, CLASS 2A	ACRE	1	1		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108	108		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108	108		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108	108		
25100115	MULCH, METHOD 2	ACRE	1	1		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1	1		
40600300	AGGREGATE (PRIME COAT)	TON	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	117	117		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15.3	15.3		
44004250	PAVED SHOULDER REMOVAL	SQ YD	469	469		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1751.6	1751.6		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		RURAL 90% FED 10% STATE 0005	---	---
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	21020	21020		
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	57824	57824		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	69	69		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	48042	48042		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16014	16014		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	48042	48042		

10 \* SPECIALTY ITEM

FILE NAME *	USER NAME * milleraj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHE NO
c:\pvc\work\p1001\milleraj\d0301120\0874	g09-shr-plan.dgn	DRAWN -	REVISED -			2101	105.106:1	WABION	9	3
	PLOT SCALE * 100.0000' / 1"	CHECKED -	REVISED -							
	PLOT DATE * 12/4/2012	DATE -	REVISED -							
						SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____		CONTRACT NO. 1666		
ILLINOIS FED. AID PROJECT										