

PAVING SCHEDULE				
STATION TO STATION	PAVEMENT REMOVAL	PCC PAVEMENT, 10"	PAVEMENT FABRIC	HMA SHOULDERS, 8"
	SQ YD	SQ YD	SQ YD	SQ YD
STA. 755+10 TO STA. 755+80	187	187	187	
LT. STA. 755+07.6 TO LT. STA. 755+78.2				51
LT. STA. 755+78.2 TO LT. STA. 757+03.2				94
LT. STA. 757+03.2 TO LT. STA. 757+73.7				51
RT. STA. 753+19.0 TO RT. STA. 753+89.5				51
RT. STA. 753+89.5 TO RT. STA. 755+14.5				94
RT. STA. 755+14.5 TO RT. STA. 755+85.0				51
TOTALS	187	187	187	392

GUARDRAIL SCHEDULE		
STATION TO STATION	SPBGR, TY A	TRAFFIC BARRIER TERMINAL, TY 1 SPL TANGENT
	FOOT	EACH
LT. STA. 755+78.0 TO LT. STA. 757+03.0	125	
RT. STA. 753+89.5 TO RT. STA. 755+14.5	125	
LT. STA. 755+28.0 TO LT. STA. 755+78.0		1
LT. STA. 757+03.0 TO LT. STA. 757+53.0		1
RT. STA. 753+39.5 TO RT. STA. 753+89.5		1
RT. STA. 755+14.5 TO RT. STA. 755+64.5		1
TOTALS	250	4