

SUMMARY OF QUANTITIES				CONSTRUCTION CODE	
				COUNTY	GALLATIN
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	100% STATE	
				ROADWAY	
				0004	RURAL
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	100	100	
44004250	PAVED SHOULDER REMOVAL	SQ YD	311	311	
44213204	TIE BARS 3/4"	EACH	416	416	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	387	387	
48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SQ YD	233	233	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	100	100	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3	3	
70200100	NIGHTTIME WORKZONE LIGHTING	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	23	23	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1475	1475	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	16	16	