



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 21, 2017

SUBJECT: FAU Route 2783 (Nagle Ave)
Project ACM-2783(008)
Section 1012-RS-2
Cook County
Contract No. 62D02
Item No. 57, March 3, 2017 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices
2. Revised page 39 of the Special Provisions
3. Revised sheets 2-4, 8 and 9 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.
Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; Estimates

MS/ck

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62D02

State Job # - C-91-419-16

Project Number

Route

County Name - COOK - -

ACM-2783/008/

FAU 2783

Code - 31 - -

*REVISED: FEBRUARY 14, 2017

District - 1 - -

Section Number - 1012-RS-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0320050	CONSTRUCTN LAYOUT SPL	L SUM	1.000				
X6030310	FR & LIDS ADJUST SPL	EACH	5.000				
X7030005	TEMP PAVT MKING REMOV	SQ FT	1,624.000				
Z0004562	COMB C C&G REM & REPL	FOOT	1,257.000				
Z0018500	DRAINAGE STR CLEANED	EACH	11.000				
Z0030850	TEMP INFO SIGNING	SQ FT	52.000				
20200100	EARTH EXCAVATION	CU YD	8.000				
21101615	TOPSOIL F & P 4	SQ YD	40.000				
25200110	SODDING SALT TOLERANT	SQ YD	40.000				
35501308	HMA BASE CSE 6	SQ YD	38.000				
40600290	BIT MATLS TACK CT	POUND	7,108.000				
40600400	MIX CR JTS FLANGEWYS	TON	16.000				
40600827	P LB MM IL-4.75 N50	TON	435.000				
40600982	HMA SURF REM BUTT JT	SQ YD	96.000				
40603340	HMA SC "D" N70	TON	890.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62D02

State Job # - C-91-419-16

Project Number

Route

County Name - COOK - -

ACM-2783/008/

FAU 2783

Code - 31 - -

*REVISED: FEBRUARY 14, 2017

District - 1 - -

Section Number - 1012-RS-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42001300	PROTECTIVE COAT	SQ YD	358.000				
42300200	PCC DRIVEWAY PAVT 6	SQ YD	110.000				
*REV 42400200	PC CONC SIDEWALK 5	SQ FT	422.000				
*REV 42400800	DETECTABLE WARNINGS	SQ FT	54.000				
44000158	HMA SURF REM 2 1/4	SQ YD	10,529.000				
44000200	DRIVE PAVEMENT REM	SQ YD	148.000				
*REV 44000600	SIDEWALK REM	SQ FT	422.000				
44201765	CL D PATCH T2 10	SQ YD	144.000				
44201769	CL D PATCH T3 10	SQ YD	251.000				
44201771	CL D PATCH T4 10	SQ YD	658.000				
60250200	CB ADJUST	EACH	5.000				
60252800	CB RECONST	EACH	1.000				
60255500	MAN ADJUST	EACH	3.000				
60300305	FR & LIDS ADJUST	EACH	5.000				
60406000	FR & LIDS T1 OL	EACH	3.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62D02

State Job # - C-91-419-16

Project Number

Route

County Name - COOK - -

ACM-2783/008/

FAU 2783

Code - 31 - -

*REVISED: FEBRUARY 14, 2017

District - 1 - -

Section Number - 1012-RS-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60406100	FR & LIDS T1 CL	EACH	4.000				
*DEL 60600605	CONC CURB TB	FOOT	25.000				
66900200	NON SPL WASTE DISPOSL	CU YD	8.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
66900530	SOIL DISPOSAL ANALY	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
*DEL 70102620	TR CONT & PROT 701501	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70102640	TR CONT & PROT 701801	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	800.000				
70300150	SHRT TRM PAVT MK REM	SQ FT	267.000				
70300220	TEMP PVT MK LINE 4	FOOT	2,837.000				
70300240	TEMP PVT MK LINE 6	FOOT	227.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62D02

State Job # - C-91-419-16

Project Number

Route

County Name - COOK - -

ACM-2783/008/

FAU 2783

Code - 31 - -

*REVISED: FEBRUARY 14, 2017

District - 1 - -

Section Number - 1012-RS-2

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300250	TEMP PVT MK LINE 8	FOOT	151.000				
70300260	TEMP PVT MK LINE 12	FOOT	159.000				
70300280	TEMP PVT MK LINE 24	FOOT	85.000				
70300520	PAVT MARK TAPE T3 4	FOOT	400.000				
78000200	THPL PVT MK LINE 4	FOOT	2,837.000				
78000400	THPL PVT MK LINE 6	FOOT	227.000				
78000500	THPL PVT MK LINE 8	FOOT	151.000				
78000600	THPL PVT MK LINE 12	FOOT	159.000				
78000650	THPL PVT MK LINE 24	FOOT	85.000				
78100100	RAISED REFL PAVT MKR	EACH	73.000				
78300200	RAISED REF PVT MK REM	EACH	73.000				
85000200	MAIN EX TR SIG INSTAL	EACH	1.000				
88600600	DET LOOP REPL	FOOT	64.000				
89502376	REBUILD EX HANDHOLE	EACH	2.000				

CONTRACT NUMBER

62D02

THIS IS THE TOTAL BID

\$ _____

NOTES:

- 1. Each PAY ITEM should have a UNIT PRICE and a TOTAL PRICE.**
- 2. The UNIT PRICE shall govern if no TOTAL PRICE is shown or if there is a discrepancy between the product of the UNIT PRICE multiplied by the QUANTITY.**
- 3. If a UNIT PRICE is omitted, the TOTAL PRICE will be divided by the QUANTITY in order to establish a UNIT PRICE.**
- 4. A bid may be declared UNACCEPTABLE if neither a unit price nor a total price is shown.**

TRAFFIC CONTROL PLAN

Effective: September 30, 1985

Revised: January 1, 2007

Traffic Control shall be according to the applicable sections of the Standard Specifications, the Supplemental Specifications, the "Illinois Manual on Uniform Traffic Control Devices for Streets and Highways", any special details and Highway Standards contained in the plans, and the Special Provisions contained herein.

Special attention is called to Article 107.09 of the Standard Specifications and the following Highway Standards, Details, Quality Standard for Work Zone Traffic Control Devices, Recurring Special Provisions and Special Provisions contained herein, relating to traffic control.

The Contractor shall contact the District One Bureau of Traffic at least 72 hours in advance of beginning work.

STANDARDS:

701011, 701101, 701301, 701311, 701427, 701606, 701701, 701801, 701901

DETAILS:

Traffic Control and Protection for Side Roads, Intersections, and Driveways (TC-10)
Typical Applications – Raised Reflective Pavement Markers (Snow-Plow Resistant) (TC-11)
District One Typical Pavement Markings (TC-13)
Short Term Pavement Marking Letters and Symbols (TC-16)
Arterial Road Information Sign (TC-22)

SPECIAL PROVISIONS:

Maintenance of Roadways
Public Convenience and Safety (Dist-1)
Keeping Arterial Roadways Open to Traffic (Lane Closures Only)
Temporary Pavement Marking (D1)
Temporary Information Signing
Automated Flagger Assistance Devices (BDE)
Pavement Marking Removal (BDE)

Revised 2-21-17