



TBM # 105: Chis. square @ of D.S. H.W. of
culvert under Montrose Ave. Elev. 635.63



Existing Structure: Footbridge with wood plank
deck, no side rails, 2 wood post support piers,
25' length.



CRYSTAL CREEK
BUILT 2010 BY
IL. DEPT. OF NATURAL RESOURCES
OFFICE OF WATER RESOURCES

NAME PLATE
(See Standard 515001)

ELEVATION



LOCATION SKETCH

DESIGN SPECIFICATIONS

2002 AASHTO Load Factor Design and
Guide Specifications for design of
Pedestrian Bridges Published by
AASHTO, August 1997

LOADING

Pedestrian Live Load = 85 psf

SEISMIC DATA

SPC = A
A = 0.05g
Site Coefficient (S) = 1.0

DESIGN STRESSES

CAST IN PLACE CONCRETE

$f'_c = 3,500$ psi
 $f_y = 60,000$ psi (reinforcement)

PRECAST PRESTRESSED UNITS

$f'_c = 5,000$ psi
 $f''_{ci} = 4,000$ psi
 $f'_s = 270,000$ psi ($\frac{1}{2}$ " ϕ strand)
 $f''_{si} = 201,960$ psi ($\frac{1}{2}$ " ϕ strand)

TOTAL BILL OF MATERIAL

Item	Unit	Total
Precast Prestressed Concrete Deck Beams (11" Depth)	Sq Ft	97
Reinforcement Bars, Epoxy Coated	Pound	1,540
Concrete Structures	Cu Yd	8.6
Name Plates	Each	1
Stone Face Finish	Sq Ft	90
Chain Link Fence, 6'	Foot	43
Portland Cement Concrete Sidewalk 6 Inch	Sq Ft	123

Designed By TMM Checked By JUF
 Drawn By JUF Checked By RLP
 1/29/2010 12:04:15 PM
 O:\Dwr\Proj\Imp\Projects\Crystal Creek\JUF\Structure No 2 General Plan and Elevation.dgn