

## BAR SPLICER ASSEMBLY ALTERNATIVES


\*\*Heavy Hex Nuts conforming to ASTM A 563, Grade C, D or DH may be used.

Bridge Deck

4'-0"

Threaded or Coil

Loop Couplers (E)



# FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS


Approach Slab

6'-0"

Threaded or Coil


Splicer Rods (E)

Bar Splicer for #5 bar Min. Capacity = 23.0 kips - tension Min. Pull-out Strength = 12.3 kips - tension No. Required =



## INSTALLATION AND SETTING METHODS

"A" :Set bar splicer assembly by means of a template bolt. "B" :Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



Bar Splicer for #5 bar Min. Capacity = 23.0 kips - tension Min. Pull-out Strength = 12.3 kips - tension No. Required =

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.


Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

- Minimum Capacity (Tension in kips) =  $1.25 \times fy \times A_t$
- Minimum \*Pull-out Strength = 0.66 x fy x A<sub>t</sub>
- Where fy = Yield strength of lapped reinforcement bars in ksi. A, = Tensile stress area of lapped reinforcement bars.
  \* = 28 day concrete

reinforcement bars.

BAR SPLICER ASSEMBLIES				
Bar Size to be Spliced	Splicer Rod or Dowel Bar Length	Strength Requirements		
			Min. Pull-Out Strength kips - tension	
#4	1'-8''	14.7	7.9	
#5	2'-0''	23.0	12.3	
#6	2'-7''	33.1	17.4	
#7	3′-5′′	45.1	23.8	
#8	4'-6''	58.9	31.3	
#9	5′-9′′	75.0	39.6	
#10	7′-3′′	95.0	50.3	
#11	9'-0''	117.4	61.8	



#### STANDARD

Bar Size	No. Assemblies Required	Location	
#5	8	Walls	
#8	10	Bottom of top slab	
#4	11	Top of top slab	
#5	9	Top & bottom of bottom slab	

BAR SPLICER ASSEMBLY DETAILS IL ROUTE 19 (IRVING PARK ROAD) OVER CRYSTAL CREEK STA. 118+56.58 COOK COUNTY S.N. 016-1198

Reinforcement

**Bars**